

CROW WING COUNTY SIO5

COUNTY SURVEYOR - 1981 TIES



11/1/47

CONTINUED
Book S-105
Page 28
CORNER DESC

FORWARD R.C.M.
Page 134
CORNER DESC

3	E-21/22	134-29	28	J 21/22	134	29
4	E-23	"	29	J 23	"	"
5	G-13	"	30	L 13	"	"
6	J-19/20	"	31	N 21/22	"	"
7	X-17	"	32	N 22/23	"	"
8	N-23	"	33	T 13	"	"
9	Z-16/17	"	34	V 15	"	"
10	N-17	134-28	35	V/W 21	"	"
11	P-17	"	36	Z 13	"	"
12	T-9	"	37	Z 15	"	"
13	V-7	"	38	Z 16/17	"	"
14	A-12/13	"	39	Z 20/21	"	"
15	A-11	"	40	A 7/6	134	28
16	A-23	"	41	A 10/11	"	"
17	A-17/20	"	42	A 17/18	"	"
18	E-17	"	43	A 21/22	"	"
19	E-11/2	"	44	C 17	"	"
20	N-21	"	45	C-21	"	"
21	R-3	"	46	C-25	"	"
22	A 17/18	134	47	C/O-B	"	"
23	E 14/15	134	48	E 23	"	"
24	O/E 21	"	49	S 10/11	"	"
25	E 15/16	"	50	S "	"	"
26	E 23/24	"	51	L-13	"	"
27	F/6 13	"	52	L-17	"	"
		"		L-21	"	"
		"		N 13	"	"

Book S-105 Page 28 CSO

INDEX

CONTRACT NO. SURVEYOR
PAGE CORNER DESC. PAGE CORNER DESC.

53	N-15	134	28	80
54	N-19	"	"	"
55	N 21/24	"	"	"

Book S-105 Page CSO

E - 21/22

T-134 N

R 29 W

FOUND 4" STEEL DISC ON 1 1/2" PIPE
STAMPED AS INDICATED IN SKETCH. NO
ORIGINAL TIES VISIBLE, TOP OF DISC
IS 8" ABOVE GROUND, AND PLAINLY
VISIBLE

15 hrs


2, MARCH, 1981

+20°, CLEAR

KP, MCKENZIE

M.E. HODEL, B.S. WHEELER

Book 8-105 Page OSO



E-23
T. 134 N
R 29 W


FOUND IN PLACE 0.6' ABOVE GROUND
5" x 3/4" STEEL OVAL ON 1 1/2" PIPE
STAMPED AS INDICATED IN SKETCH
NO ORIGINAL OR OTHER TIES VISIBLE

2 HRS

2, MARCH, 1981
+20°, CLEAR
K.P. MCKENZIE

ME, HODEL, B. WIESELOH

Book S-105 Page CSO



NO. 447

NATIONAL

6-13

T 134 N

R 29 W

FOUND IN PLACE 2" PIPE 0.5'

BELOW BITUMINOUS PIPE 15' 5" E

WEST OF EXISTING 4"

THREE EXISTING TIES ARE;

12" RED OAK, N 26° E, 47.60

12" RED OAK, N 60° W, 23.19

12" RED OAK, S 22° W, 38.93

(NOTE: THESE TIES ARE TO THE FACE OF EXISTING LOWER BLAZES)

NO EVIDENCE OF ORIGINAL TIES

VISIBLE THERE IS A RECENT BRUSH

LINE TO THE EAST,

1.5 HRS


2, MARCH, 1981

+20°, CLEAR

K.P. MCKENZIE


M.E. HODEL, B.S. WESELOH

Book S-105 Page CSO



EXIST. TIE 12\"/>

S - 19/20
T 134 N
R 29 W



FOUND IN PLACE 1 1/2" PIPE, TOP
IS FLUSH WITH GROUND. BUT
BENT TO THE SOUTH DUE TO
THE ICE BREAK UP.

TWO EXISTING TIES ARE

BRASS BT. 10" ELM S 52 E 31.47

10" ASH S 21 W 94.18

NOTE: ALL TIE DISTANCES ARE TO THE BOTTOM
OF PIPE.

NO EVIDENCE OF ORIGINAL TIES
VISIBLE

15 HRS


2, MARCH, 1981
+20°, CLEAR
K.P. MCKENZIE
M.E. HODEL, B.S. WESELOH

Book S-105 Page CSO

N O R T H

L O C A T I O N

L A K E



X-17

T-134 N

R-29 W

34 — 35

FOUND IN PLACE CROW WING CO.
CAST IRON MONUMENT APPROX 0.1'
ABOVE GROUND NO ORIGINAL TIES
VISIBLE, FOUND FOR THE TREES IN
GOOD CONDITION, SEE SKETCH FOR
DIMENSIONS

2 HRS.

Book S-105 Page CSO


2, MARCH, 1981

+20° CLEAR

K.P. MCKENZIE

M.E. HOPEY, R.S. WESELOH

⑦



N-23
T-134 N
R-29 W

FOUND IN PLACE 2" IRON PIPE
0.3' ABOVE GROUND. 4.2' WEST OF PER-
METER FENCE FOR BRAINERD INTER-
NATIONAL RACEWAY
NO EVIDENCE OF ORIGINAL OR
EXISTING TIES

25 HAS

9, MARCH, 1981
+25° OVERCAST
K.P. MCKENZIE
M.E. HODEL, B.S. WESLOH

Book S-105 Page CSO

BRAINERD

WIRE MESH FENCE WITH
STEEL FENCE POSTS

INTERNATIONAL

2" IRON PIPE

16" JACK PINE

4.2' CNTR. OF FENCE POST
TO CNTR. OF IRON


16" JACK PINE

RACE

WAY

8" RED OAK

10" RED OAK



Z- 10/17
T 134 N
R 29 W

21

FOUND IN PLACE 2" IRON PIPE
1.0' ABOVE GROUND. 28' EAST OF EDGE
OF WATER. FOUND IN PLACE TWO
1924 (LOUIS KNUDSEN) BEARING TREES

12" RED OAK, NO. 53 1/2 E 40.0'
12" RED OAK, N 80 E 38.5'


NOTE: THESE TREES ARE BOTH DEAD AND
BROKEN OFF, BUT THE BLAZES ARE STILL
PLAINLY VISIBLE.

2.5 HRS

9, MARCH, 1981
+25° OVERCAST
K.P. MCKENZIE
M.E. HODEL, S.S. WESLON

9

Book S-105 Page CSO



N. + 17
T 134 N
R 28 W

15	14
22	23


FOUND IN PLACE 2" IRON PIPE
FLUSH WITH GROUND, FOUND APPARENT
REMAINS OF ONE 1934 BT. (7" JACK
PINE N 30° W 11.7'). ALSO FOUND BLAZES
IN 8" JACK PINE N 82° W 14.0'.

2482

(10)

13, MARCH, 1981
+40° P.C.
K.P. MCKENZIE
M.E. HOEL

Book S-105 Page CSO



P-7

T 134N

R 28 W


22 23

FOUND IN PLACE 2" IRON PIPE
0.3' ABOVE GROUND. FOUND EXISTING
TIES AS SHOWN IN DIAGRAM

2 HR'S

13, MARCH, 1981
T40 P.C.
K.P. MCKENZIE
M.E. HODEL

Book S-105 Page CSO




T-4
T 134 N
R 28 W

FOUND IN PLACE 100d SPIKE
0.2' BELOW GRADE. FOUND ONE ST.
IN PLACE.

1 HR

15 MARCH, 1981
T40° PC
K.P. MCKENZIE
M.E. HOEL

Book S-105 Page CSO



24' 5 GRAVEL RD


R 28 W

FOUND N PLACE 100' SPIKE
0.2' BELOW GRADE N & GRAVEL RD.
FOUND EXISTING TIES AS SHOWN
IN SKETCH, THESE TIES ARE SMALL
NAILS IN THE SIDE OF TREE

1 NR.

13, MARCH, 1981
40° RC,
KRMCKENZIE
ME. HODEL

(13)



A- 12/13
T 134 N
R 28 W

93/135/28
4/124/28

FOUND IN PLACE 2 1/2" IRON PIPE

0.3' ABOVE GROUND. FOUND 2 BLAZED

OAKS, 14" BUR OAK N 89° W, 33.76°

14" RED OAK S 14° E, 78.90°

I RE-BLAZED THESE AS THEY WERE

GROWN OVER AND MADE ONE ADD.

TIE,

THE PROPERTY OWNER TO THE

SOUTH TOLD ME THIS PIPE HAD BEEN

LYING ON ITS SIDE FOR SOME TIME

AND THAT A SURVEYOR HAD RE-SET

IT. AND HE THOUGHT IT WAS IN THE

WRONG PLACE BECAUSE HIS GARAGE

WAS A BIT OVER THE LINE.

2 HRS

16, MARCH 1981
+35° CLEAR
K.P. MCKENZIE
M.E. HODEL, B.S. WESELOM


(14)

Book 3-105 Page 650

NORTH

LONG

LAKE



A-11
T-134 N
R 28 W

33/135/28
4/124/28


FOUND IN PLACE 2 1/2" IRON PIPE
2.0' ABOVE GROUND, WE ROUGH CHAINED
2006' FROM M.C. TO THE EAST, AND
PIPE FITS GOOD ON EXT. OF FENCE
LINE FROM THE NORTH, NO EXISTING
TIES VISIBLE.

NOTE: TIES I MADE ARE TO
THE BOTTOM OF PIPE AS IT IS BENT
SLIGHTLY TO THE SO.

2 HRS.

Book S-105 Page CSO

16, MARCH, 1981
+35°, CLEAR
K.P. MCKENZIE
ME HODEL, B.S. WESSELOH




A - 23
 T - 134 N
 R - 28 W
 183/135/128
 30/135/28
 1/134/28

FOUND IN PLACE 1/2" IRON PIPE
 IN APPROX. E GRAVEL RD 0.4' BELOW
 ROAD GRADE, WITH THREE EXISTING
 TIES AS FOLLOWS
 6" RED OAK N 16° W, 36.32
 6" JACK PINE N 19° E, 36.31
 POWER POLE S 38° E, 45.12

1.5 HRS

16, MARCH, 1981
 +10° CLEAR
 K. P. MCKENZIE
 MET. MODEL, BS. WESLOH

Book SLICE Page CSO



NO. 447 NATIONAL

A- 19-20
T- 134 N
R- 28 W

35/135/20
2/134/28


FOUND IN PLACE 1 1/2" IRON PIPE
0.5' BELOW GROUND. FOUND THREE
EXISTING D.N.R. TIES AS INDICATED
BY SKETCH. THESE TIES ARE 1" DISC.
AND NAIL IN SIDE OF TREE

1.5 HRS

Book S-105 Page CSO

16, MARCH, 1981
40° CLEAR
K.P. MCKENZIE
M.E. HOEL, B.S. WESLOH

(17)



NO. 447

NATIONAL

E-17

T-134N

R 28W

3	2
10	11

FOUND IN PLACE CROW WING CO.
CAST IRON MONUMENT FLUSH WITH
GROUND, FOUND EXISTING TIES AS
SHOWN IN SKETCH.

2 HRS

(18)


20, MARCH, 1981

440° CLEAR

K.P. MCKENZIE

M.E. HODEL, B.S. WESELOH

Book S-105 Page CSO



E- 11/12
T 184 N
R 28 W

FOUND IN PLACE 1/2" PIPE, 1' ABOVE
GROUND ON TOP OF RIDGE @ EDGE
OF LAKE. FOUND 3 EXISTING BTS
AS FOLLOWS

6" ASPEN, N 65° E,	5.68	DYING
8" ASPEN, S 54° E,	6.68	DEAD
18" EUM STUMPS, 32° W,	11.68	BRASS BT- DEAD STUMP


THESE BTS ARE ALL DEAD OR DYING
SO I MADE 3 NEW TIES, SHOWN
IN SKETCH.

2 HRS.

23, MARCH, 1981
440° CLEAR
K.P. MCKENZIE

ME. HUEL, BS. WESLOH
Page CSO

(19)



N-21
T 134 N.
R 28 W

14 13
23 24


FOUND NPLACE 2" IRON PIPE
WITH R.R. SPIKE IN TOP, 0.8' ABOVE
GROUND. FOUND 2 EXISTING BLAZES
AS SHOWN IN SKETCH. 2 1/2 NORTH
OF 2'x1' ROCK. NO OTHER EXIST
BL'S

25 WRS

(20)

124 MARK, 1701
+58° CLEAR
K.P. MCKENZIE
M.E. HOVEL

Book S-105 Page CSO



PLOWED

FARM

FIELD

2" IRON PIPE
WITH R.R. SPIKE
IN TOP

WOOD FENCE
POST, FALLEN
DOWN

EXIST. BLAZE IN
12" ASPEN

EXIST. BLAZE IN
12" ASPEN

TWIN 2 1/2 4" BURNED

EXIST BLAZE IN
12" RED OAK

R-3
T 134N
R 28W

19
—
30

FOUND 1/2" IRON PIPE 1"
BELOW GRADE. FOUND TIES
IN PLACE AS SHOWN.


2.0 HRS

30, MARCH 1981

+40° CLOUDY (21)
K.P. M. KENZIE
N.E. HOPEL

B.S. WESELOH

Book S-105 Page CSO



B.T. IN 4" RED OAK

NO. 447



1152 W
186.10

C.R.

#146

5252 W
141.91

524 E
141.91


B.T. IN P.P.

B.T. IN

8" RED OAK



A-17/18
T-134-N
R 29 W




CHAINED EAST 910' FROM
N.E. CORNER SEC. 2 TO WESTERLY
SLOPE OF ICE RIDGE (ALONG LAKE
AND EAST OF HWY. 371), FOUND STUMP
OF 36"± WHITE PINE, POSSIBLE OR-
IGANAL BT., NO MONUMENT, NO OTHER
BT.

2 HRS

12 FEB, 1981
+25° PC,
K.P. MCKENZIE
M.G. HODEL, B.S. WESELOH

22



E-14/15
T 134 N
R 29 W

3
15

LOOKED FOR BOTH ME'S
ON NARROW POINT BETWEEN LOVE
LAKE AND GULL LAKE. BOTH SIDES
OF POINT BADLY ERODED BY ICE
BREAK-UP. DIDN'T FIND EITHER
CORNER OR ANY EXISTING TIES.

2 HRS.

Book S-105 Page CSO


GULL

APPROX. COR.
LOCATION


LAKE

LOVE

LAKE



D/E-21
T 134 N
R 29 W



DROVE TO PUBLIC ACCESS
FOUND FENCE LINE ON EASTERLY
SIDE OF ACCESS. CHECKED ENTIRE
AREA, ALONG THE NORTH SHORE OF
RD. LONG LAKE, FOUND NOTHING

FOUND IN PLACE 2-2" PIPE
APPROX. 30' SO. OF THE SOUTH-
EASTLY SHORE OF ROUND LAKE.
FOUND NO BT'S. - NOTHING
TO INDICATE EITHER PIPE IS
THE M.C.

Z.M.S.

12, FEB. 1981
+25° OVERCAST
KP/McKENZIE
ME HODEL, SS. WISEMAN

(24)

Book S-105 Page CSO


N
NO SCALE

ROUND LAKE


30' E - 30' S

WOOD FENCE

NORTH
ARROW



E- 15/16
T 134 N
R 29 W



FOUND 1/2" PIPE & CAP #3091.
AND LATH MARKED LOT 8 ON OLD
FENCE LINE, APPROX 10' EAST OF
EASTERLY SHORE LOVE LAKE. NO
BTS OR INDICATION THAT THIS IS
THE M.C.

2 WRS.

Book S-105 Page CSO


17, FEB, 1981

+25° PC.

KP MCKENZIE

MC, HOVEL, BS, WESSON

(25)



NO. 447

NATIONAL

E-23/24

T 134 N

R 29 W


FOUND 1 1/2" PIPE IN APPROX
M.C. LOCATION. NO BT'S BUT NUM-
ERONS 1/2" IRONS TO THE NORTH
AND EAST R.L.S. # 3091 & 13336

2 HRS

11
12

Book S-105 Page CSO

9 MARCH, 1901
75° OVERCAST
K.P. MCKENZIE
W.C. HODEL BS. WESLOH



F/G-13
T 134 N
R 204 W

9

FOUND 1 1/2" PIPE AT TOP OF
STEEP BANK TO GULL LAKE. SOME
FLAGGON OF STUMP NEXT TO IRON.
SEEMS TO BE MC. BUT NO BT'S.
OR OTHER EVIDENCE TO BEAR THIS
OUT.

142.

(27)

4, FEB. 1981
40 P.C.
K.P. MCKENZIE
M.E. HODEL, B.S. WESTLOH

Book S-105 Page CSO

GULL LAKE

1 1/2" PIPE

20 FEBRUARY, 1981
 440, P.C.
 K. P. MCKENZIE
 ME. HODEL, 85, WESELOW

(28)

Book S-105 Page CSO


J-21/22
 J-K-21
 134 W
 R 29 W

FOUND 2" PIPE ON WELL DEFINE
 LINE TO THE SOUTH. APPEARS TO
 BE J-K-21, BUT CANNOT BE-IF
 IT WERE THE SEC. COR. COULD HAVE
 BEEN SET.

NOTE: THE EXISTING SHORELINE
 WOULD INDICATE THIS LINE SHOULD
 BE MOVED FURTHER WEST.

DIDNT FIND J-21/22

2 HRS.



J-23
 J-23/24
 R 134 N
 R 29 W

12
 13


DIDN'T FIND EITHER, J-23
 APPEARS TO FALL IN GRAVEL
 PIT, BUT DIFFICULT TO ESTABLISH
 EAST-WEST LINE. NUMEROUS IRONS
 ALONG EAST SIDE OF BITUMINOUS
 RD. ON NORTH-SOUTH LINE, AND
 ALONG WEST SHORE OF NORTH
 LONG LAKE

2 HRS.

27 FEB, 1981
 40° 45' N
 K. P. MCKENZIE
 ME. HOEL, B.S. WESTERN

(29)

Book 8-105 Page CSO



T 134 N
R 29 W




FOUND SEVERAL 1/2" PIPE & CAP.
R.S. # 172100 ON FENCE LINE TO THE
NO OF COR., FOLLOWED FENCE TO
APPROX. LOCATION, BUT COULD NOT
FIND CORNER - NO PTS

2 HRS.

(30)

460, P.C.
K.P. MCKENZIE
W.E. HOEL, A.S. WESTERH

Book S-105 Page 050



N-21/22
T131 N
R-29 W

13
24


ROUGH CHAINED DOWN BRUSH
LINE FROM N.E. COR. SEC. 24
TO APPROX. MC. LOCATION FOUND
1/2" RE-BAR, NO BT'S DID NO
TIE OUT

2 HE

2

Book S-105 Page CSO

20 FEB 1981
+35 PC.
K.P. MCKENZIE
M.E. HONOLULU BS, WESTLOA



1/2" RE-BAR

NO. 80. 371 2
NO. 80. 371 2

NO. 447

NATIONAL

N-22/23
T 134 N
R 29 W

13
24


ROUGH CHAINED FROM N.E. COR.
SEC. 24. DOWN BRUSH LINE AND
ACROSS MUD LAKE TO APPROX M.C.
LOCATION. FOUND WOOD 1"x2" WITH
FLAGGIN NO BT'S. DID NOT TIE OUT

2 HR.

32

29 FEB, 1981
#35 P.S.
K.P. MCKENZIE
W.C. HOVEL, B.S. WESSELOH

Book S-105 Page CSO



T-13

T-134 N
R 29 W

28

27

COULDNT FIND ANYTHING TO
CHAIN FROM, SEARCHED APPROX.
LOCATION FROM USGS. MAP.
DID NOT FIND.

246,

29 FEB, 1981

436° P.C.

K.P. MCKENZIE

ME. HODEL, B.S. WESLOH

33

Book S-105 Page CSO



NO. 447



NATIONAL

T 134 2
R 29 2
34

SEARCHED APPROX LOCATION
FROM U.S.G.S. MAP FOUND SOME
BLUE FLAGGING ON A NORT-SO. LINE
AND A 1" PIN IN OLD RT. RD TO
THE SOUTH OF COR. COULD NOT
FIND ANY RTS OR EVIDENCE OF
CORNER.

2 HR.

K.P. MCKENZIE
M.E. HOEL, B.S. WHEELER



10, MINICA, 1781
+40° CLEAR
K.P. MCKENZIE

35

M.E. HODGE, B.S. WHEELER

Book S-105 Page CSO

BIT

HUWY

← DIRT RD.

STORM SEWER
OUT FALL

RED

SAND

LAKE

SEARCHED ENTIRE AREA @
SO. END OF ROAD AND ALONG
THE NORTH SHORE OF RED SAND
LAKE. DIDN'T FIND ANYTHING.
THERE WAS A STORM SEWER
PUT IN RECENTLY, CORNER MAY
HAVE BEEN DESTROYED THEN.

112.

Z-13
T-134N
R 29 W

33 34
4 3

(2)


WALKED IN ON OLD RD. FOUND
FENCE ON APPROX SO LINE SEC.
34 FENCE GOES SO. @ APPROX
S 1/4 COR. AND RUNS 1320' WEST
THEN SO. SEARCHED AREA NEAR
FENCE COR. 2640' WEST FOR
COR. IN SWAMP FOUND NOTHING.

4.5 HR

11/10/11
+40 CLEAR
K.M. MCKENZIE
M.E. MODEL, BSWESLON

36

Book S-105 Page CSO



Z-16/17
T 134 N
R 29 W 3 2

CHAINED 721.38' ACROSS
LAKE FROM Z-16/17. NO MON.
NO. EXISTING TIES


W

1 H2

OVERCAST
K.P. MCKENZIE
M.E. MODEL, B.S. WESLOH

(37)

Book S-105 Page CSO



Z-20/21
T 134 N
R 29 W

35/10/29

2/133/29

CHAINED EAST FROM SD,
1/4 COR. SEC. 35 37.26 CHAINS
TO WESTERLY SHORE OF RED SAND
LAKE DIST. FITS OK, BUT COULDN'T
FIND COR. OR ANY TIES.


4/1

2 1/2

13 MARCH, 1981
+28° PC,
K.P. MCKENZIE
M.E. WDEL, BS. WESTLOM

38

Book S-105 Page CSO



A - 7/8
T 134 N
R 28 W

312

SEARCHED APPROX LOCATION
FROM U.S.G.S. MAP DID NOT FIND
CORNER, BUT, NUMEROUS 1/2" IRONS
(#3091) ALONG LAKE SHORE.

17, FEB, 1981
+40° OVERCAST
K.P. MCKENZIE
ME. MODEL, B.S. WESLEY

39

Book S-105 Page CSO



1/2" IRONS

NORTH LONG LAKE

25

A-10/11
T 134 N
R 28 W

2/

CHAINED WEST 7.32 CHAINS
WEST OF NO. 1/4 SEC. 4 DID NOT
FIND M.C. OR ANY TIES

1 HK

3/3

4

10, MARCH 1991
FSS, CLEAR
K.F. MCKENZIE
M.E. HOEL, BSWESLOV

40

Book 8-105 Page CSO



NO. 1/4 SEC. 4

NORTH

LONG

LAKE

NO. 447

NATIONAL


A-17/18
T 134 N
R 28 W

✓ FOUND EAST-WEST FENCE
LINE NO. OF HSE, BUT COULD
NOT FIND COR.
LADY @ NEARBY HOUSE SAID
THE LAKE HAD RISEN OVER THE
YEARS AND SHE HAD NEVER SEEN
THE CORNER.

1.5 HX

11, 120, 1700
440° OVERCAST
K.P. MCKENZIE
M.C. MODEL, B.S. WESELOK

Book S-105 Page CSO



NO. 447

NATIONAL

A-21/22
T 134 N
R 28 W

~



FOUND 100d SPIKE AND 1/2"
IRON (R.L.S. 3091) ON SKINNY POINT
ON SORENSEN LAKE. DIDNT FIND
ANY TIES. EITHER COULD BE THE
M.C.

1412

42

408 RC
K.D. MCKENZIE
ME. MODEL, 85. WESTLAW

Book S-105 Page CSO



NO. 447

NATIONAL

C-17
T 134 N
R 28 W

DROVE TO APPROX. AREA FROM
U.S. MAP. APPEARS TO FALL NEAR
POWER LINE AND WAS PROBABLY DESTROYED
DURING CONSTRUCTION. DID NOT FIND
CUR. OR ANY TIES

14R.

STANLEY, PA
458° CENAR
K.P.M. KENZIE
W.C. ROSE, B.S. WESLOK

43

Book S-105 Page CSO

C-21
T 134 N
R 28 W

SEARCHED APPROX. LOCATION
FROM USGS MAP UNDER POWER
LINE. FOUND NOTHING.

certified by P. N. A. 1-29-81
NO. 326
T.H.

1 HR

(44)

7/1/1981
4580 CLEAR
KPMCKENZIE
WRE, HADEL, B.S. WESLEY

Book S-105 Page CSO


NO. 447

NATIONAL

C-25

T 134 N

R 28 W



SEARCHED APPROX LOCATION FROM
USGS MAP, ALONG NW SHORE OF
POND FOUND NOTHING.

1 HR.

24 MARCH 1981

TSB, CLEAR.

K.P. MCKENZIE

M.F. NOBEL, B.S. MIESELOH

(45)

Book S-105 Page CSO

CD-13
T 134 N
R 28 W

3

CHAINED NO. FROM SW COR. SEC.
3. BE43 CHAINS TO A POINT IN
NO. LONG. LAKE. FOUND A 1" GAL-
VANIZED PIPE ON SHORE APPROX
15' SHORT OF GOVT. DIST. DID
NOT TIE OUT - NO VISIBLE TIES

1 HR.

18 FEB. 1981
440 P.M.
K.P. MCKENZIE
W.E. HODEL, BS. WESLOH

46

Book S-105 Page CSO

NORTH

LONG

LAKE

COR. LOCATION

1" GAL. PIPE

← SW COR. SEC. #3

E-23
T 134 2
R 28 3

SEARCHED APPROX. LOCATION
FROM USGS. MAP LOW SWAMPY
AREA MANY TAMARAC & SPRUCE
COULD NOT FIND COR. OR ANY
EXIST. TIES.

1 HR.

24 MARCH 1981
458° CLEAR
K.P. WYKENZIG
M.E. HODEL, B.S. WESSELOH

Book S-105 Page CSO

(47)

5-10-11
 5-11-12
 T 134 W
 R 28 W

CHAINED WEST 40 & 55.50 CHAINS
 FROM S.E. COR. SEC. 9 ALONG REMAINS
 OF OLD FENCE LINE. DIDNT FIND
 EITHER CORNER OR ANY EXISTING
 TIES.

2 HRS.

(48)

+ 40, P.C.
 K.P. MCKENZIE
 M.E. HODEL
 B.S. WESLOH


Book S-105 Page CSO

NORTH

70
70
70

LAKE

REMAINS OF OLD
 FENCE LINE




T 134 N 16
R 28 W


CHAINED WEST ALONG OLD FENCE
LINE FROM E. BIT. RD. HIT N-S.
FENCES @ 1300' ± & 2620' ±, BUT
NO CORNER OR EXISTING TIES

1412

4460 PC
McKENZIE
HONOLULU, WESSEL



E. BIT. HWY 2



BARBED WIRE FENCE

NO. 447

NATIONAL

L-17
T 134 N 15
L 28 W

ROUGH CHAINED APPROX. DIST
WEST FROM E. WY. 25 ALONG
OLD E-W FENCE LINE TO CREST
OF HILL NEAR TRAIL DID NOT
FIND COR. OR ANY TIES

14R.

55

W. WINKER, TDI
445° CLEAR.
K.P. MCKENZIE
W.E. HODGE, BS. WHEELAH.

Book S-105 Page CSO



E CREEK
BED

TRAIL

E. WY. 25 →

L-21
T 134 N
R-28 3


CHAINED NORTH 264D FROM
THE S.E. CORNER OF SEC. 14
FOUND BARBED WIRE FENCE
THAT CURVES AROUND A SWAMPY
AREA, BUT NO CORNER OR VISIBLE
TIES.

2/11/1

15

23 MARCH, 1981
+45° CLEAR
K.P. MCKENZIE

Book S-105 Page CSO



N-13
T 134 N
R 28 W

16	15
21	22


FOLLOWED OLD BARBED WIRE
FENCE LINE WEST FROM APPROX.
SO. 1/4 COR. SEC. 15 @ 2 BIT.
HWY THROUGH SWAMPY AREA BE-
YOND A SMALL CREEK TO A
SMALL POINT OF HIGH GROUND.
FOUND A SPOOL OF BARBED
WIRE @ APPROX CORNER BUT
NO POST OR TIES SEEM TO
FIT. THE FENCE CONTINUES TO
THE WEST

20 HRS


52

17 FEB, 1981
+40° CLEAR
K.A. INKENZIE
MELROD, BS, WESTERN

Book S-105 Page CSO



N-15
T 134 N
R 28 W




SEARCHED ENTIRE ROADBED
WITH MAGNETIC LOG. @ INT.
OF FENCE LINE TO THE WEST
AND OLD ROAD TO THE
THE EAST COULD NOT LOCATE
CORNER OR ANY TIES.

L.H.R.

18, FEB 1981
+40° P.C.
K.P. MCKENZIE
M.C. KODEL, B.S. WESLOH

53

Book S-105 Page CSO



N - 19
T - 1341 N
R 28 W

115
114
23


ROUGH CHAINED EAST ALONG
A BARBED WIRE FENCE FROM THE
E OR THE OLD HWY. 1320' MORE
OR LESS TO A FENCE INTER-
SECTION (FENCE'S EA. - WE. & SO.)
DID NOT FIND THE CORNER OR
ANY TIES.

1 HR.

(54)

10, MARKER, PLOT
+ 45° CLEAR
K R MCKENZIE
ME MODEL, B2 WESELA

Book S-105 Page CSO



NO. 447

NATIONAL

N-19
 N 21/22
 T 134 N
 R 29 W

ROUGH CHAINED EAST FROM
 SW. COR. SEC. 13 1197 FT ±
 THIS POINT APPEARS TO FALL IN THE
 MISS. RIVER.

1 HR

23, MARCH 1981
 4:50 CLEAR
 K. D. MCKENZIE
 M.E. MODEL, B.S. WISELAH

Book S-105 Page CSO

