

Crow Wing County Surveyor

No. S-115

S-115 - 1342203

X

INDEX (T 137-14-27)

PAGE	INDEX	CORNER DESCRIPTION
7-8	E-5	SEC COR 5-6-7-8 / 137-27
9-10	F/G-5	MC 7-8 / 137-27 45-56 CL. N. Sec Cor
11-12	E-9	SEC COR 4-5-8-9 / 137-27
13-14	G-9	1/4 COR 8-9 / 137-27
15-16	G-13	1/4 COR 9-10 / 137-27
17-18	J-9/10	MC 9/14 / 137-27 80-66 CL. W. of Sec Cor
19-20	J-11	1/4 COR 9-16 / 137-27
21-22	J/K-13	MC 15-16 / 137-27 62-38 CL. N.
23-24	J/K-25	MC 13 / 137-27 - 18 / 137-26 65-47 CL. N
25-26	N-5	SEC COR 17-18-19-20 / 137-27
27-28	N-11	1/4 COR 16-21 / 137-27
29-30	P-1	1/4 COR 19-137-27 / 24-137-28
31-32	P-9	1/4 COR 20-21 / 137-27
33-34	R-21	SEC COR 23-24-25-26 / 137-27
35-36	R-25	SEC COR 24-25 / 137-27 - 19-30 / 137-26
37-38	V-1	SEC COR 30-31 / 137-27 - 25-26 / 137-28
39-40	V-3	1/4 COR 30-31 / 137-27
41-42	V-5	SEC COR 29-30-31-32 / 137-27
43-44	V-15	1/4 COR 27-28 / 137-27
45-46	X-13	1/4 COR 33-34 / 137-27
47-48	Z-3	1/4 COR 31 / 137-27 - T 136

INDEX (T 137-14-27)

PAGE	INDEX	CORNER DESCRIPTION
51-52	V-5	SEC 1/4 29-30-31-32 / 138-27
53-54	T-5	1/4 COR 29-30 / 138-27
55-56	R-5	SEC COR 19-20-29-30 / 138-27
57-58	V-13	SEC COR 27-28-33-34 / 138-27
59-60	X-13	1/4 COR 33-34 / 138-27
61-62	P-17	1/4 COR 22-23 / 138-27
63-64	J-17	SEC COR 10-11-14-15 / 138-27
65-66	N/23-24	MC 13-24 / 138-27 29-81 CL. W.
67-68	N/21-22	MC 13-28 / 138-27 75-91 CL. W.
69-70	N/21-22	MC 13-24 / 138-27 66-51 CL. W.

No. S-115

INDEX (T 136-1-27)

PAGE INDEX CORNER DESCRIPTION

123-124 R/22-23 MC 24-25/136-27 50.91 CH WEST
 125-126 R-23 1/4 COR 24-25/136-27
 127-128 R/24-25 MC 27-28/136-27 29.35 CH W
 129-130 T-17 1/4 COR 26-27/136-27
 131-132 T-21 1/4 COR 25-26/136-27
 133-134 T/20-21 MC 25/26/136-27 31.39 CH N

No. S-115

NO. 447

WELDING

INDEX (T 136-R 27)

PAGE INDEX CORNER DESCRIPTION

73-74 C-21 1/4 COR 1-2/136-27
 75-76 E-21 SEC COR 1-2-11-12/136-27
 77-78 E/20-21 MC 2-11/136-27 14.17 CH W
 79-80 F/6-21 MC 11-12/136-27 51.31 CH N
 81-82 F/6-17 MC 10-11/136-27 56.66 CH N
 83-84 G-5 1/4 COR 7-8/136-27
 85-86 G-9 1/4 COR 8-9/136-27
 87-88 G-13 1/4 COR 9-10/136-27
 89-90 G-17 1/4 COR 10-11/136-27
 91-92 G-21 1/4 COR 11-12/136-27
 93-94 J-13 SEC COR 9-10-15-16/136-27
 95-96 J-15 1/4 COR 10-15/136-27
 97-98 J-17 SEC COR 10-11-14-15/136-27
 99-100 J-21 SEC COR 11-12-13-14/136-27
 101-102 L-17 1/4 COR 14-15/136-27
 103-104 L-21 1/4 COR 13-14/136-27
 105-106 N-13 SEC COR 15-16-21-27/136-27
 107-108 N-15 1/4 COR 15-22/136-27
 109-110 N-19 1/4 COR 14-23/136-27
 111-112 N-21 SEC COR 13-14-23-24/136-27
 113-114 P-21 1/4 COR 23-24/136-27
 115-116 R-17 SEC COR 22-23-26-27/136-27
 117-118 R-19 1/4 COR 23-26/136-27
 119-120 R-21 SEC COR 23-24-25-26/136-27
 121-122 R/22-23 MC 24-25/136-27 55.97 CH W

No. S-115

NO. 447

WILSON

1

E-5
T137-R27

6 5
7 8

SEC. COR 5-6-7-8 / 137-27

FOUND 2" IP WITH OVAL CAP FLUSH

PRIOR SURVEYS

D. COULTER 1970 FOUND 2" I.P. WITH OVAL CAP

DOOR 506, PG 128


TIME SPENT 3/4 HA

E-5

T137-R27

6 5
7 8

Aug 14, 1981
D. COULTER
P. BARN



9 F/6-5
T137-227

7-8

MEANDER COR 758 / 137-27
45.50 CH. N. OF SEC. COR.

FOUND 1 1/4" I.P. IN CONCRETE
FLUSH WITH GROUND

PRIOR SURVEYS

KNUDSEN, 1923 SET W.C. BOOK 24 WSW R 021
D. COULTER, 1970 FOUND I.P. IN CONC. BOOK 506 / 152


TIME SPENT 3 1/4 HR

F/6-5
T137-227

7-8

NO S-115

Aug 11, 1974
D. COULTER
P. R. ADAMS



RUSH LAKE

E-9

T 137-R27

5 4

8 9

SEC. COR 4-5-8-9 / 137-27

FOUND 3/4" I.P. DOWN 0.2 IN APPROX
E OF GRAVEL ROAD

PRIMA SURVEY

D. COULTER 1970 FOUND I.P.

BOOK 509
PAGE 7

TIME SPENT 3/4 HR

E-9

T 137-R27

3

8

4

9

AUG 11, 1981

D. COULTER
P. BRADY

NT. S-115

18" NORWAY PINE
SINGLE LOW
BLAZE

28" WHITE PINE
OLD B.T.

18" NORWAY PINE

N 49° 00'
76.30

IRON PIPE

6" NORWAY PINE

20" NORWAY PINE
OLD B.T.

ALL TREES DOUBLED BLAZED APPROX.
1' ± ±' ABOVE GROUND UNLESS
OTHERWISE NOTED

X

B G-9

T 137-R 27

8-9

Quarter Cor 8-9 / 137-27

Found 1/4" 100N PIN IN APPROX 1/2 OF
ROADS E-W & N

PRIOR SURVEYS

1917-1919	J. CURD	FOUND SET	BOLT I.P.	CWC BOOK PG 325
1924	"	FND	INPL	
1950	D. ANDERSON	FND	INPL	BOOK 509 PAGE 7
1970	D. COULTER	FND	INP.	

TIME SPENT 3/4 Hr

G-9


T 137-R 27

8-9

Aug 11, 1981

D. COULTER
P. BACON

N. S-115



ALL TREES DOUBLE BLAZED
APPROX 1' & 5' ABOVE GROUND

15 G-13

T 137-227

9-10

G 13

T 137-227

9-10

Aug 11, 1981
D. COULTER
P. BACON

QUARTER COR 9-10 / 137-27


FOUND 1/2" I.P. 0.1 BELOW SURFACE
IN APPROX 4 INT.

PRIOR SURVEYS

1917-1919	J. CURRO	SET. A.P.	CWC BOOK A PAGE 325
1950	D. ANDERSON	SET MON TO RELOC OLD PIPE	BOOK 62 PAGE 54
1953	"	NEW TIES	BOOK 76 PAGE 49
1974	D. COULTER	FND. MPL.	BOOK 517 PG 11

TIME SPENT 3/4 HR

N 2-115



ALL TREES DOUBLE BLAZED
APPROX 1' F5" ABOVE GROUND

J-9/10
T137-227

MC 80.61 ch w. of Sec 1 Cor

Found 1 1/4" IP Flush on top of BANK

PA10A SURVEYS

1970 U.S.C.E FOUND IN PL

1972 D. COULTER FOUND IN PL

BOOK A.C.E. 01, 0200
PAGE 2

BOOK 517 Pg 5


TIME SPENT 3/4 Hr

J-9/10
T137-227

7
16

AUG 11, 1981
D. COULTER
P. BACON

N. S-115



NO. 447
WILSON

J-11
T137-R27

QUARTER COR 9-14 / 137-27

FOUND 1" IP 0.4 ABOVE SURFACE

PRIOR SURVEYS


1920	L. Knudsen	FNO. INPL.	BOOK 9 WSN pg 75
1961	D. Anderson	FNO. INPL.	BK 130, PG 56
1972	D. Coulter	FNO. INPL.	BK 517, PG 9

TIME SPENT 3/4 HR

J-11
T137-R27

Aug 11, 1981
D. COULTER
P. BACON

NK S-115



ALL TREES DOUBLE PLAZED
APPROX. 1' ± 5' ABOVE GROUND

21
J/K-13

T 137-R 27

M.C. 15-16/37-27 62.38 CH. N. of

SEC. COR

FOUND 1 1/2" IP 0.3 ABOVE SURFACE

PRIOR SURVEYS

1970 U.S.C.E. FOUND NPL

1971 D. COULTER FOUND NPL

BOOK ARE/01
Pg 17, 18, 20

BK 12, PG 91

TIME SPENT 3/4 HR

J/K-13


T 137-R 27

16-15

AUG 11, 1981
D. COULTER
P. BACON

22

S-115



23

J/K - 25

T 137-R27

T137-R27

13-78

R27-R26

MC/13-137-27/18-137-26 65.42 CL N.

FOUND 2" IRON PIPE W/OVAL CAP ON N.

SHORE OF O'BRIEN LAKE AT WATERS

EDGE. PIPE LEANING NORTH. TIES

TAKEN TO POSITION OF PIPE STRAIGHTENED

PRIOR SURVEYS

1922	J. CURTO	Set 2" x 20" STAKE FOR TEMP. COR.	CWC BRA PG 87
1922	Raudsen	Found INPL	BR 22/40N PG 35
1971	D. Coulter	Found INPL	BR 510, PG 144
1947	Anderson	Found INPL	BR 48, PG 32
1956	"	Found INPL - MOVED BY ICE ACTION	BR 92, PG 62

TIME SPENT / HOUR

T137-R27

13-78

R27-R26

J/K-25

T 137-R27


AUG 12, 1981


D. COULTER

P. BACON

24

No. S-115

ALL TREES HAVE SINGLE LOW
BLADE UNLESS OTHERWISE NOTED



25
 N-5
 T 137-R27

18 17
 19 20

SEC. COR 17-18-19-20 / 137-27
 FOUND 10" SQUARE CONC. MON.
 0.3 ABOVE SURFACE

N-5
 T 137-R27

18 17
 19 20

SEC. COR 17-18-19-20 / 137-27
 FOUND 10" SQUARE CONC. MON.
 0.3 ABOVE SURFACE


PRIOR SURVEYS

1922	KNUDSEN	FND. IN PL.	BK 22-WSN PG 24
1926	"	STONE MON	BK 25-WSN PG 63
1953	D. ANDERSON	CONC MON IN PL.	BK 79-AG 30
1969	U.S.C.E	" "	BK ACE 01 CW 30 PG 34
1969	D. COULTER	" "	BK 507/52

TIME SPENT 3/4 HR

ALL TAGS DOUBLE BLAZED
 APPROX 1' ± 5' ABOVE GROUND

N-11
T137-R27



Quarter Cor 16-21 / 137-27


Found 1" Iron Pipe 0.5 Below
Surface in N-S Trail

Prior Surveys


1907	U.S.C.E	Set Core Mon	190502 - AG 110 CWC 01 - P6137
1922	J. Curo	FND IN PL	AG 09 PG 55 C50
1956	D. Anderson	120N Pipe Mon	BK 93 - PG 13
1963	D. Coulter	FND IN PL	BK 12 - PG 51
1970	USCE	FND IN PL	ACE 01 - PG 12 CWC50

Time Spent 3/4 HR

N-11
T137-R27



No. 8-115



ALL TREES DOUGLE BLAZED
APPROX 1' ± 5' ABOVE GROUND

T137 - T137
24-019
R28

Aug 12, 1981
D. COULTER
P. BACON

P-1

T137-R27

MO. 5111

QUARTER COR 19-137-27 / 24-137-28

FOUND 2" I.P. w/ OVAL CAP 1.0 ABOVE
SURFACE

5" Norway Pine

16" Norway Pine

NO. 447

N 40° W
71.74

12" Norway Pine

IRON PIPE

576.90 W
85.15

18" Norway Pine

N 20° E
86.15

16" RED OAK

ALL TREES DOUBLE BLAZED
APPROX 1' ± 5' ABOVE GROUND

PRIOR SURVEYS:

Set 2" x 20" STAKE
FOR TEMP. CORCWCO B12A
PG 162BK 25 W 51 N
PG 24

Set From D.S.B.T.

FND 14PL

BK 76 - PG 37

BK 527 - 59

1922

J. CURT

1926

KNUDSEN

1953

P. ANDERSON

1978

D. COULTER

TIME SPENT 1 HR

P-9
T 137-227

20-21

QUARTER COR 20-21 / 137-27

FOUND 8" SQUARE CONC MON WITH U.S.C.E.
BRASS CAP 0.5 ABOVE SURFACE

PRIDA SURVEYS

1922 J. Euro FOUND U.S. MON / MPL ACE 09 PG 55 C 30

1933 J. Preston FOUND CONC MON / MPL BK 170 PG 14 CHD

1954 D. Anderson FND / MPL BK 84 - PG 32

1956 " " " BK 93 - PG 13

1959 " " " BK 125 - PG 5

1965 " " " BK 158 - PG 64

1969 U.S.C.E. " " " BK ACE 01 PG 14 CWC 30

1972 D. Coulter " " " BK 518 PG 74

TIME SPENT 3/4 HR

P-9
T 137-227

20-21

Aug 11, 1981
O. Coulter
P. Bacon

N. S-115

4' ABOVE ROAD

8" WHITE OAK

8" RED OAK (1972 B.T.)

10" RED OAK


12" RED OAK

8" RED OAK

10" RED OAK (1972 A.T.)

10" RED OAK

ALL TREES DOUBLE BLAZED
APPROX 1' ± 5' ABOVE GROUND



23 24
26 25

R-21
T137-A27

23 24
26 25

Aug 12, 1981
D. COULTER
P. BACON

34


SEC COR 23-24-25-26 / 137-27

FOUND 1 1/4" I.P. 0.2 BELOW SURFACE
IN BLACKTOP ROAD, 9' ± SO. OF E

Prior Surveys:

1904	Garrison	Set Post from USDT	1904 BK - PG 29
1921	Curo	Set 3/4" x 10" I.P. for TEMP Cor	CWC BKA, PG 567
1921	Kaudsen	Iron Pipe Set by Garrison INPL	BK 21 WSW PG 21
1928	"	I.P. IN PL	BK 32 WSW PG 3
1965	J. PERKIN D.N.R.	FND. IN PL	DNR/LM/I LEB/96

Time Spent 3 1/4 Hr



ALL TREES DOUBLE BLAZED
APPROX. 1' ± 5' ABOVE GROUND

R-25
T 137-R 27

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

1151
24 19
R 27 25 30 R 26

SEC CO 24-25/137-27 - 19-30/137-26
FOUND BENT 2" I.P. 3'2 FEET
BELOW SURFACE 2.5' T.N. of ϕ
OF BLACKTOP ROAD
SET 1/2" X 24" I.P. 0.3 BELOW SURFACE

PRIOR SURVEYS
1904 GARRISON POST FROM ORIG. BIT. 1904 BOOK, PG 27
1921 KNUDSEN SET 1/2" X 24" I.P. 0.3 BELOW SURFACE 2.5' T.N. of ϕ BK 21 WSN PG 21
1928 KNUDSEN NEW BIT. MON = WOOD POST BK 32 WSN, PG 2
1922 J. CURRO SET 3/4" X 10" I.P. FOR TEMP. COR. CW 20 BK A PG 60

TIME SPENT:
8/12/81 1 1/2 HR } 2 3/4 HRS
9/21/81 2 1/4 HR }

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27


T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27

T 137 24 19
R 27 25 30 R 26
R-25
T 137-R 27



ALL TAGS DOUBLE BLAZED
APPROX 1' 55' ABOVE GROUND

V-1
T 137-227

Seq. Cor. 30-31/137-27 + 25-36/137-28
FOUND 10" SQUARE CONC. MON. 0.5' ABOVE
SURFACE

PRIOR SURVEYS

1922	J. CURD	Set 2" x 20" STAKE FOR TEMP. COR	CWCO BKA PG 624
1953	D. ANDERSON	END CONC MON	BK 79, PG 29
1955	"	" "	BK 87, PG 11
1962	C.G. GULTER	" "	BK 604 PG 2
1969	U.S.C.E	" "	BK AGE of CWCSO PG 31


TIME SPENT 3/4 HR

1 171
25 30
36 31
R28 R27

V-1
T 137-227

T 137 T 137
25 30
36 31
R28 R27

Aug 12, 1981
D. GULTER
P. BACON



CROSS LAKE

ALL TREES DOUBLE BLAZED
APPROX. 1' ± 5' ABOVE GROUND
UNLESS OTHERWISE NOTED

V-3
T137-R27

31

QUARTER COR 30-31 / 137-27

FOUND 6" DIAM ROUND CONC MON
WITH USCE BRASS CAP. THIS MON
APPARENTLY REPLACED 2" IP W/OVAL CAP
FOUND BY ME IN JULY 1969. OLD TIES
INDICATE NEW MON TO BE APPROXIMATELY
0.22' E-S-E OF ORIGINAL POSITION.

PAID SURVEYS:

1923	KINDSEN	FND. INPL.	BR 24 WSN PG 25 AND BK 25 WSN PG 12
1969	D. COULTER	FND. INPL.	BK 506, PG 101
1969	USCE	FND INPL.	BK ACIE 01 PG 32 CUC50
1968	D. ANDERSON	FND INPL.	BK 155, PG 68

TIME SPENT 3/4 HR

V-3
T137-R27

30
31

AUG 12, 1981
D. COULTER
P. BAISON

10" WHITE OAK
SINGLE LOW BLADE


10" WHITE OAK
SINGLE LOW BLADE

10" NORWAY
PINE

10" RED
OAK


6" BIRCH

ALL TREES DOUBLE MEASURED
APPROX 1' ± 5' ABOVE GROUND
UNLESS OTHER WISE NOTED



1

TIME	SPENT
	3/4 Hr



V-15
T137-R27

34

QUARTER COR. 27-34 / 137-27

FOUND 1 1/2" IP 0.1' BELOW SURFACE

PRIOR SURVEYS

1904 GARRISON SET POST FROM USPT'S
1915 MURPHY CO. ENG. FOUND COR.


BLK 45, PG 1 COLLEGE

TIME SPENT 2 1/4 HR

V-15
T137-R27

34

AUG 12, 1981
O. COULTER
P. BACON



ALL TREES DOUBLED
APPROX 1" & 5' ABOVE GROUND

X-13
T 137-027

33-034

QUARTER COR 33-34 / 137-27

FOUND 1 1/2" I.P. 0.4' ABOVE SURFACE

PRIOR SURVEYS

1968 D. Coulter Found I.P.

1973 " "


OK 501 / 19.8
OK 50 PG 46

TIME SPENT 3/4 HR

X-13
T 137-027

33-034

Aug 11, 1981
D. Coulter
P. Bacon



ALL TREES DOUBLE BURNED
APPROX 1' & 5' ABOVE GROUND

1311

T 136

Z-3
T137-R27

SOUTH 1/4 COR SEC 31 / 137-27

FOUND 1 1/4" X 22" I.P. LAYING DOWN
RE-SET FROM 3-1973 TIES BY
D. COULTER STILL STANDING. CORNER
FALLS ON CUT BANK 13' S SOUTH
OF E OF E-W GRAVEL ROAD.
DUG OUT BANK AND SET CORNER
0.5' BELOW ROAD SURFACE

PRIOR SURVEYS

1973 D. COULTER FOUND INPL. 84513, P4103

TIME SPENT 1 1/4 HR


T137-R27
31

T 136

Aug 18, 1981
D. COULTER
P. BACON

Z-3

T137-R27



ALL TIES DOUBLE PLAZED
APPROX 1' ± 5' ABOVE GROUND
UNLESS OTHERWISE NOTED

V-5
T138-R 27

30 29
31 32

SEC. COR. 29-30-31-32 / 138-27

FOUND R.R. SPK 0.1 Below Surface
over Bent 2" I.P. 0.5 Below Surface
IN & INT. BLACKTOP ROADS N-S & E

PRIOR SURVEYS
1905 Garrison SET I.P. from
1921 J. Curro SET MON USST STUMPS
1937 Knudsen FUD 5 MON COR AGE 09
1939 Woods " " " BK 39, PG 46
1968 D. Cawther FOUND BOLT OVER BK 39, PG 5
1969 USC E FUD I.P. AGE 03
PG 14 C.W.C.S.O.

TIME SPENT 1 HR

52

V-5
T138-R 27

30 29
31 32

Aug 18, 1991
D. Cawther
P. Bacon

No. S-115

16" RED OAK
16" TWIN RED OAK
12" RED OAK
TRANSMISSION LINE
POWER POLE
IRON PIPE
BLACKTOP ROAD
BACKLAP
REF. MARK (OVAL CAP)
(BENT)

ALL TREES DOWN & PLAZED
APPROX 1' ± 5" ABOVE GROUND

52

R-5
T138-R27

19 20
30 29

SEC COR 19-20-29-30 / 138-27

AFTER EXTENSIVE SEARCH FOUND
4 MONUMENTS OF A 5 MONUMENT
CORNER IN HEAVY UNDERGROWTH
N.E. REF MON IS MISSING
ALL MONS ARE 2" IP ROUND CAP ON
CORNER - OVAL CAPS ON REF MONS.

PRIOR SURVEYS:


1905 GARRISON Post from USBT Stumps 1904 Book PG 115
1921 CURA SET MON. AGE - 09 PG 61 850
1939 ESTREM FND 2" IP ROUND CAP BX 200 17 PG 64 250
PART OF 5 MON COR

TIME SPENT 4 1/2 HRS

R-5
T138-R27

19 20
30 29

Aug 18, 1981
D. Coulter
P. Bacon



ALL TREES DOUBLE BLAZED
APPROX 1' FS' ABOVE GROUND

4-13

T138-427

Sec. Cor 27-28-33-34 / 138-27

FOUND 2" I.P. w/ROUND CAP 0.12 BELOW
SURFACE AT APPROX. 4 PI OF
ROADS IN SW

Prior Surveys

1971	D. Coulter	FOUND	INPL	BK 512	P 683
(MAY BE OTHER RECORDS - DID NOT HAVE COUNTRY RECORD SHEET)					

TIME SPENT:	3/4 HR
1. What is the purpose of this experiment?	To determine the effect of temperature on the rate of reaction between hydrogen peroxide and potassium iodide.
2. What are the reactants and products of the reaction?	Reactants: Hydrogen peroxide (H_2O_2) and Potassium iodide (KI). Products: Water (H_2O) and Iodine (I_2).
3. What is the balanced chemical equation for the reaction?	$2H_2O_2(aq) + 2KI(aq) \rightarrow 2H_2O(l) + 2KI(aq) + I_2(aq)$
4. What is the independent variable in this experiment?	Temperature of the reaction mixture.
5. What is the dependent variable in this experiment?	Rate of reaction, measured by the time taken for a fixed volume of iodine to be produced.
6. What are the controlled variables in this experiment?	Concentration of hydrogen peroxide, concentration of potassium iodide, and volume of reaction mixture.
7. What is the hypothesis for this experiment?	The rate of reaction will increase with increasing temperature.
8. What is the procedure for this experiment?	1. Prepare a series of reaction mixtures at different temperatures (e.g., 10°C, 20°C, 30°C, 40°C, 50°C). 2. Measure a fixed volume of hydrogen peroxide and potassium iodide solutions. 3. Mix the solutions and start a timer. 4. Stop the timer when a fixed volume of iodine is produced (indicated by a color change). 5. Record the time taken for the reaction to occur at each temperature.
9. What are the results of the experiment?	The rate of reaction increases with increasing temperature. For example, the time taken for a fixed volume of iodine to be produced decreases as the temperature increases.
10. What is the conclusion of the experiment?	The rate of reaction between hydrogen peroxide and potassium iodide increases with increasing temperature.


V-13

T.138-P.27

28 27 Aug 19, 1981

D. Coulter

P. BACON



ALL TREES DOUBLE BLAZED
Approx 1' 5" ABOVE GROUND

59

X-13

T138-227

33-34

QUARTER COR 33-34 / 138-27

FOUND 1 1/2" I.P. 0.3 BELOW SURFACE

15' WEST OF 4 OF TRAIL

264411' So. of Sec. Cor.

NO PRIOR SURVEYS KNOWN TO EXIST
OTHER THAN ORIG GOUT.

TIME SPENT 2 1/2 HRS

X-13

T138-227

33-34

AUG 19, 1981

D. CAUCHER
P. BAUM

60

No. S-115

0 SEC COR IN PL

264411' --
15'

18" NORWAY PINE

29.10

44.30W

58.00W

63.43

44" JACK PINE

9" NORWAY PINE

58.70E

63.60

12.00W PINE

53.60W

49.29

51.11E

56.45

10" WHITE OAK

6" NORWAY PINE

ALL TREES DOUBLE BLAZED
APPROX 1' 5" ABOVE GROUND

P-17
T 138-227

QUARTER COR 22-23 / 138-27

FOUND 1 1/4" I.P. 0.4 BELOW SURFACE
IN DIRT ROAD

PRIOR SURVEYS:


1920 J. Curo Set 2" x 20" STAKE From USBT STUMPS BOOK A EWCO pg 462
1955 D. Anderson Set I.P. From Curo Ties BK 85, pg 52

TIME SPENT: 3/4 Hr

22-0-23

P-17
T 138-227
Aug 19, 1981
D. COVETER
P. BACON

NO. S-115



ALL TAGS DOUBLED
APPROX 1' 5" ABOVE GROUND


10 11
 15 14
 J-17
 T138-227

SECTION COR 10-11-14-15 / 138-27
 FOUND 1 1/4" 1 P. 1' ABOVE SURFACE

PRIOR SURVEYS:
 1922 J. CURD Set 2" x 20" STAKE FOR TEMP. COR. cweo BK A PG 628
 1939 DEIMAN C.C.C. OCCUPIED COR. BK 10, PG 7 P.N.R. W.L.
 1955 D. Anderson Set Cor From Topog. BK 85, PG 53

TIME SPENT 1 1/4 HR

J-17
 T138-227
 10 11 Aug 19, 1981
 15 14 D. COULTER
 P. B. H. CON



ALL TREES DOUBLE BARBED
 APPROX 1' ± 5' ABOVE GROUND

N/23-24
T138-R27


M.C. 13-24 / 138-27 29.81 CH.W.
of sec. cor
FOUND MINN. CONV. DEPT MON
0.5' ABOVE SURFACE

PAIDR SURVEYS:
1968 D. COULTER
FOUND MINN. CONV. DEPT MON

TIME SPENT 1 HR

N/23-24
T138-R27

Aug 19, 1981
D. COULTER
P. BACON



ALL TREES DOUBLE BLADED
APPROX 1' ± 5' ABOVE GROUND

N/21-22
T138-227

24

M.C. 13-24/138-27 75.01 E.W. of SEC COR

FOUND NO EVIDENCE OF CORNER
OR BAG TREES

PRIOR SURVEYS
1942 KNUDSEN 1" IP set from old stumps, etc BK 61, PG 19
1962 V. Anderson M.C. PIPE IN PL BK 137, PG 35

TIME SPENT 1 HR

N/21-22
T138-227

24

AUG 19, 1981
D. COULTER
P. BACON

NO. S-115

FOUND NO EVIDENCE
OF CORNER OR KNUDSEN
B.T.S. - NO VISIBLE
LINE OF OCCUPATION

TRAP LINE LAKE

TRAP LINE

N/21-22

T 138-R 27

13
0
24

M.C. 13-24/138-27 66.51 ch W of Sec Ctr

Found 1 1/4" x 4' IP Very Loose &
 ONLY STUCK IN GROUND ABOUT
 1/2 FOOT - NO OTHER EVIDENCE
 EXCEPT DUGS FALL ON E-W
 YARD LINE - EVIDENCE TO
 FLIMSY TO ACCEPT AS CORNER
 DID NOT TIE

PRIOR SURVEYS:

1942 KNUDSEN SET 1" I.P. FROM
 OLD STAMPS, ETC. BK 61, PG 19

1962 D. ANDERSON PIPE IN PL. BK 137, PG 35

TIME SPENT 3/4 HR

Aug 19, 1981

D. BOULTER

P. BACON

13

0
24

N/21-22

T 138-R 27

ING. S-115

FOUND PIPE NOTED
 ON OPPOSITE PG.
 EVIDENCE TO
 FLIMSY TO ACCEPT
 OR TIE

YARD LINE

EAGLE
LAKE

C-21
T136-227

2-0-1

QUARTER COA 1-2 / 136-27

FOUND NO EVIDENCE OF CORNER
OTHER THAN TIMBER CRUISER LINESNO PRIOR SURVEY RECORD KNOWN TO
EXIST OTHER THAN ORIG. GOVT.

TIME SPENT - 1 HR


C-21

T136/227

2-0-1

SEPT 21, 1981
D. COULTER
P. BACON

No. S-115



75

E-21
T136-R227

2 1
11 12

SEC. COR 1-2-11-12 / T136-R227

FOUND NO EVIDENCE OF CORNER
OTHER THAN TIMBER CRUISER LINES

PRIOR SURVEYS
1904 GARRISON

SET POST FROM
U.S.B.T.'S

1904 DOOR, PG. 6

TIME SPENT 1 HR

E-21


T136-R227

2 1
11 12

SEPT 21, 1944
D. COULTER
P.B. & CON

76

No. S-11B



17 E/20-21
T 136-R27

7
11

MC 2/11 - 136-27 1417 ch. w. of Sec Cor
RAW W. ON MAG FROM APPROX. SEC COR POSITION
FOUND NO EVIDENCE OF CORNER

NO FURTHER SURVEYS KNOWN TO EXIST
OTHER THAN ORIG. GOV'T.

TIME SPENT 3/4 HR

E 20/21
T 136-R27


7
11

SEPT 21, 1961
D. COULTER
P. BAACON

28

NO. S-115

CORNER FALLS IN
SWAMPY RIVER
BOTTOM LAND. FOUND
NO EVIDENCE



11 0 12

F/G-21	11	0	12
T 136-R27			
M.C. 11-12	T 136-R27	51.31	ch W. of Sec. Cor

RAN SO. ON MAP FROM APPROX. SEE. COR. POSITION				
FOUND NO EVIDENCE OF CORNER				
OTHER THAN TREE LINES				

PAROLA	SURVEYS
1904	GARRISON

GARRISON	No B.T.s	FOUND	1904 AK, PG 7
----------	----------	-------	---------------

Time	Spent	3/4 HR
------	-------	--------

F/G-21
T136-R27

11-0-12
SEPT 21, 1981
D. COLQUETER
P. BACON

	No.	S-115
	Sec. Cor	
	Approx location	

FOUND NO EVIDENCE
OF M.C.

Pine River

MATURE
NO 2 WAY
PLANTING
+ 20 years old

F/G - 17
T 136 R 27

10 11

M.C. 10-11 / 136-27 52.66 Ch. N. of 500. Cor
FOUND ORIG 3. W. U.S.B.T. STILL
STANDING IN GOOD CONDITION. TREE
WAS 8" NORWAY PINE IN 1843 NOW 26" DIAMETER
CUT SECTION OUT OF TREE 2' HIGH X 0.8 WIDE
X 0.7 DEEP TO FACE OF ORIGINAL TREE
FACE OF ORIG. TREE SOMEWHAT ROTTED
BUT SOME SCRIBING STILL LEGIBLE AS
FOLLOWS "T 136 R 27" CAN BE READ WELL
WITH MORE SCRIBING BELOW WHICH
APPEARED TO BE "S-10" - REST ROTTED OUT
SET 3/4" X 3 1/2' I.P. 0.8 ABOVE SURFACE FROM F.
FACE OF ORIGINAL TREE TRUNK


PAID SURVEYS:
1912 GARRISON ORIG B.T. STANDING PG 4
Set Post From 1912 Book

TIME SPENT
8/27/81 1 1/2 HR } 2 1/2 HRS
8/28/81 2 HRS }

F/G - 17
T 136 R 27

10 11

ON OCTOBER 15, I
TERRY J. BENLEY (COUNTY SURVEYORS OFFICE)
USBT AND TURNED THE SAID IRON PIPE
FLUSH AND PLACED A SQUARE ALUMINUM
CAP 2" X 2" OVER TOP OF SAID PIPE
SAID CAP HAS "COUNTY SURVEYOR" STAMPED
ON FACE. *Red Dye*



ALL TREES DOUBLE BLAZED
APPROX 1' ± 5' ABOVE GROUND

AUG 27, 1981
AUG 28, 1981
O. COULTER
P. HANCOCK

G-5

T 136-R27

QUARTER COR T-8 / 136-27

FOUND 6" DIAM. ROUND CONC. MON. TOP
BROKEN OFF, 1.0' BELOW SURFACE, 7' ±
N of E of E-W GRAVEL RD.

PRIOR SURVEYS

1912	GARRISON SET POST	1912 BK, PG 2
1934	PRESTON CEMENT MON	BK 216, PG 19 CHO?
1953	D. ANDERSON FND CONC. MON.	BK 73, PG 72

TIME SPENT 1 1/4 HRS


7-0-8

G-5

T 136-R27

7-0-8

AUG 27, 1981
D. CARTER
P. BACON



ALL TREES DOUBLE PLAZED
APPROX 1' ± 5' ABOVE GROUND

8A

G-17

T136-R27

10-11

QUARTER COR 10-11 / 136-27

FOUND 6" DIAM ROUND CONC. MON
 0.1 BELOW SURFACE IN EAST WHEEL
 TRACK OF N-TS TRAIL. MON LEANING
 BADLY. DUG OUT AND RE-SET
 0.5 BELOW SURFACE

PRIOR SURVEYS

1912 GARRISON Set Post from USBTs 1912 BK, PG 5
 1934 PRESTON FMO CONC. MON 614216 CHD, P412

TIME SPENT 1 1/4 HR

G-17

T136-R27


10-11

AUG 27, 1981

D. COULTER

P. BACON

No. S-115



ALL TREES DOUBLE BLAZED
 APPROX 1' ± 5' ABOVE GROUND

G-13
T136-R227

9-10-10

QUARTER COR 9-10 / 136-27

FOUND 6" DIAM. ROUND CONC. MON
1.4' BELOW SURFACE IN APPROX. E OF
BLACKTOP ROAD. SET 3/4" X 16" I.P. OVER
MON.

PRIOR SURVEYS:


1912 GARRISON Post from USAT
1934 PRESTON FND CONC. MON

TIME SPENT 2 3/4 HR

G-13
T136-R227

9-10-10, D. COULTER
P. BACON

SEPT. 21, 1981



ALL TREES DOUGLE BLAZED
APPROX 1' ± 5' ABOVE GROUND

91

G-21

T136-1227

11-0-12

QUARTER COR 11-12/136-27

MADE SEARCH FOR CORNER IN
GENERAL AREA INDICATED BY
USGS QUAD MAP. AREA IS
IN DENSE UNDERBRUSH. FOUND
NO EVIDENCE OF CORNER

PRIOR SURVEYS:

1904 GARRISON POST - ORIGIN DOWN 1904 BOOK, P. 8

TIME SPENT 3/4 HR

G-21

T136-227

11-0-12

AUG 27, 1981


D. COULTER

P. BACON

92

No. S-115

FOUND NO EVIDENCE OF
CORNER OTHER THAN
N-X LOGGING LINE



NO. 447

W. B. BOWEN

93

J-13

T136-1227

9

10

16

15

SEC COR 9-10-15-16 / 136-27

MADE SEARCH FOR CORNER IN DENSE

UNDERBRUSH IN GENERAL AREA

INDICATED BY U.S.G.S. QUAD MAP.

FOUND 10" DEAD JACK PINE STUMP 15' TALL

BLAZED ON 4 SIDES (OLD BLAZES)

TREE ALSO HAS MINN - CONS - FORESTRY

TAG - ALSO FOUND 2 BLAZED LINE

TREES TO WEST. ALL NORWAY

WHITE PINE LOGGED OFF

FOUND NO OTHER EVIDENCE OF COR

NO PRIOR SURVEYS KNOWN TO EXIST

OTHER THAN ORIG. GOVT.

TIME SPENT 2 1/4 HRS

J-13

T136-1227

9

10

16

15

AUG 27, 1981

D. COULTER

P. BACON

94

No. 8-115

TRAIL

1200'

+

POND

± 600'

LAK

NO. 447

M. 1437

FOUND NO EVIDENCE
OF CORNER OTHER
THAN AS NOTED ON
OPPOSITE PAGE

95

J-15
T136-R27

10
15

QUARTER COR 10-15 / 136-27

MADE SEARCH FOR CORNER IN
GENERAL AREA INDICATED BY
USGS QUAD MAP. ALL FOUR
QUADRANTS LOGGED AND
REPLANTED. FOUND NO
EVIDENCE OF CORNER

NO PRIOR SURVEYS KNOWN TO EXIST
OTHER THAN ORIG. GOVT.

TIME SPENT 1 HR

96

AUG 28, 1981
D. COUNTER
P. BACON

10
15

J-15
T136-R27

No. 111

NO EVIDENCE OF
AREA PLANTED
AND LOGGED
BY

TRAIL

NO. 447

NO. 447

J-17
T 136-R27

10 11
15 14

Aug-27, 1981
O. COULTER
P. BACON

SEC. COR 10-11-14-15 / 136-27


FOUND OVAL CAP REF. MONUMENTS IN
NE-NW & SW QUADS. ALSO GOT
METAL DETECTOR READING AT POINT
FOR CORNER IN BLACKTOP ROAD. SET
1/2" x 12" I.P. FLUSH IN & 20 FEET
REF. MONS.

REF. MONS. ARE 2" I.P. W/OVAL CAPS

PRIOR SURVEYS

1907	GARRISON	POST FROM ORIG BTS STANDING	1905 BOOK, PG 108
1912	"	FOUND I.P. AND ORIG AT STANDING	1912 BOOK, PG 5
1920	J. CUREO	SET 5 MON COR	CWC BKA, PG 472
1934	Preston	FND. 5 MON COR IN PL	84216 CHD, PG 11

TIME SPENT 1 HOUR



ALL TACKS DOUBLE BLAZED
APPROX. 1' x 5' ABOVE GROUND

99
J-21
T 136-R27

SEC. COR 11-12-13-14 / 136-27

AFTER EXTENSIVE SEARCH, FOUND
5 MONUMENT CORNER. CORNER
IS FLUSH WITH SURFACE. REF. MONS
VARY FROM FLUSH TO 0.4 ABOVE
GROUND.
CORNER IS 2" IP W/ ROUND CAP
REF. MONS ARE 2" IP W/ OVAL CAPS

PRIOR SURVEYS

1904 GARRISON POST-ORIG AT STANBRO 1904 BOOK PG 8
1920 J. COLO SET 5 MON. COR BK ?


TIME SPENT 5 HOURS

11 12
14 13

11 12 SEPT 28, 1951
D. COULTER
13 14 P. BACON

J-21
T 136-R27

No. S-115



ALL TREES DOUBLE BLAZED
APPROX 17' ± 5" ABOVE GROUND

6-17

T136-127

15-0-14.

QUARTER COR 14-15 / 136 -27

FOUND 5 MON. COR.	REF MON'S TO
NW & SE IN 6000 COND.	ALL OTHERS
BENT. SET $\frac{1}{2}$ " X 2'	1. P. FROM REF
MONS NW & SE	FLUSH IN & BLK TOP RD.
REF. MONS. ARE	2" IP. w/OVAL CAPS

Prior Surveys

1907	GARRISON	SET POSIT	1905 BK, Pg 108
1920	J. CURTO	SET 5 MON COR	CURTOBK A, Pg 472
1928	Knutsen	FNO. INPL.	BK 32 WSN, Pg 16
1934	Preston	FNO. 5 MON COR INPL.	BK 216 CHD Pg 10

TIME	SPENT	/ HOUR
------	-------	--------

T 136-1227

T 136-1227

6-17

LO
—
—
1
C)

Z

Aug 28, 1981
D. Coulter
O. A. Con

41-51

ALL TREES DOUBLE BURNED
APPROX. 1" & 5' ABOVE GROUND

103

L-21

T 136-27

14-13

QUARTER COR 13-14 / 136-27

FOUND 2" IP W BROKEN ROUND CAP - FLUSH
AND REF MARKS IN NW-NE & SE QUADS.
ALL FLUSH 2" IP W/ OVAL CAPS
NW REF MARK BADLY BENT

PRIOR SURVEYS

1920 J. C. CROO SET 5 MON COR W/ 8 MA, 19472

TIME SPENT 2 1/2 HRS

104


SEPT. 28, 1921
D. COUNTER
P. BACON

14-13

L-21

T 136-227

NO. 447



ALL TREES DOUBLE BLAZED
APPROX 1' & 5' ABOVE GROUND

106

N-13

T 136-227

16

15

21

22

SEC. COR 15-16-21-22 / 136-27

FOUND 3/4" I.P. UP 1 FOOT IN TALL

MARSH GRASS NEAR SO. EDGE OF

SWAMP FROM 1965 DNR TIE TREES.

1965 DNR TIE TREES NOW ALL DEAD

5' BROKEN OFF. S.E. TREE DOWN COMPLETELY

PRIOR

SURVEYS

1965

PEAPICH 3/4" I.P. UP 1 FOOT

D.N.R. ELYC SWAMP

DNR / 2M / 12

CWO / 208 / 70

TIME SPENT

13/4 HR

N-13

T 136-R-27

16

15

21

22


Aug 28, 1981

D. COULTER

P. BACON

No. S-115

106



ALL TREES DOUBLE BLAZED

APPROX 1' ± 5' ABOVE GROUND

105
167

15
22

15
22

15
22

N-15
T 136-227

15
22

Aug. 28, 1961
D. COULTER
P. BACON

108

QUARTER COR 15-22 / 136-27


FOUND 6" DIAM ROUND CONE, MON
0.4' ABOVE SURFACE

PRIOR SURVEYS

1928 KNUDSEN Cone Mon by INGRAM BK 32 W 5, Pg 16

TIME SPENT 1 1/4 Hrs

No. S-115



ALL TREES DOUBLE BLAZED
APPROX. 1' ± 5' ABOVE GROUND

$$\frac{m}{2}$$


2' ±	N. of	£
------	-------	---

1934	Preston	FND 5 Mod. Car. Inpr.	BK 216 CHO, Pg 6
------	---------	-----------------------	------------------

[illegible]

Aug 28, 1981
D. Coulter
P. Bacon

513



ALL TREES DOUBLE BLAZED APPRX.
1' 5' ABOVE GROUND UNLESS
OTHERWISE NOTED

T 136-427

QUARTER COR 23-24 / 136-27

FOUND LARGE SPR IN E N-S BLK. TOP
ROAD. DOES NOT FIT APPARENT
OCCUPATION LINE TO WEST.
(Cleared yard line)
CORNER SHOULD BE VERIFIED BEFORE USING

Prior Surveys

(Oid Not Have County Record Sheet)

TIME	SPENT	1 1/2 Hours
------	-------	-------------


9-21

T 136-R 27

23-024

Sept 29, 1981
D. Coulter
P. Bacon

114



115

R-17

T136-R27

22 23

27 26

SECTION COR 22-23-26-27 / 136-27

FOUND 5 MON CORNER - SEC. COR #

NE REF MON LEAVING. TIES TO

STRAIGHTENED POSITION OF SEC. COR.

SEC. COR IS 2" IP W/ROUND CAP

REF MONS ARE 2" IP W/OVAL CAPS

ALL MONS $\pm$ 0.8' ABOVE SURFACE

PRIOA SURVEYS

1920 J. CURRO Set 5 MON COR CWC BKA, PG 472

TIME SPENT 4 HOURS

R-17


T136-R27

22 23

27 26

ALL TREES DOUBLE
BLAZED APPROX.
1'-5.5' ABOVE GROUND

No. S-115



116

SEPT 18, 1981

D. COULTER

P. BACON

17

R-19

T 136-227

23

26

QUARTER COR 23-26 / 136-27

RAN W. ON MAG FROM SEC. COR

FOUND NO EVIDENCE OF CORNER

OTHER THAN NEW FENCE AND NEW

SPIKE AS SHOWN ON OPPOSITE

PAGE. DID NOT ACCEPT SPIKE

AS CORNER SINCE IT WOULD APPEAR

TO HAVE BEEN SET AS APPROX.

CORNER ONLY

NO PRIOR SURVEY RECORD KNOWN TO EXIST
OTHER THAN ORIG. GOV'T.

TIME SPENT 2 1/2 HRS

R-19

T 136-227

23

26


Sept 18, 1981

D. COULTER

P. B. A. CON

115

NO. S-115



R-21
T136-227

FOUND NO EVIDENCE OF OLD
5 MON CORNER - SWAMP HAS BEEN
DREDGED & NEW ROAD CONSTRUCTED.
OBTAINED TWO TIES FROM CO. HWY.
DEPT. & FOUND SPK. IN & NEW
ROAD, SEC. COR. PER CO. HWY DEPT
REPLACED SPK. WITH "12" X 24"
I.P. FLUBH (HWY TIES WERE TO NED IN
SIDE OF TREES - NEW TIES ARE TO BLAZED FACE)

PRIOR SURVEYS


1904	GARRISON	FND. INCL	CR BOOK, PG 67
1922	T. CURT	Set 5 MON COR	CRWBK B, PG 23
1934	Preston	FND 5 MON COR INCL	CR 216 CHD, PG 2

Time Spent

Sept 4, 1981	3/4 HR	} 2 HRS
Sept 29, 1981	1 1/4 HR	

R-21
T136-227Sept 4, 1981
Sept 29, 1981
D. Coulter
P. Bacon

N.C. S-115



ALL TREES DOUBLE BLAZED
Approx 1' & 5' ABOVE GROUND

121
R/22-23
T136-227

24
0
25

MC 24-25/136-27 55.97 ch. w. of Sec Cor
RAN EAST ON MAG FROM SEC COR
FOUND NO EVIDENCE OF MG

No. Prior Survey Record Known to Exist
OTHER THAN ORIG. GOV'T.

TIME SPENT 2 HRS


R/22-23
T136-227

122

SEPT 18, 1961
D. COULTER
P. BAACON

NO. 5-11

NO. 447



NO EVIDENCE OF MG
FOUND. - NO VISIBLE
LINES OF OCCUPATION

103

R/22-23
T 136-227

24
24
0
25

MC 24-25/136-27 50.91 CH W. of Sec Cnr

RAN W. ON MAG. FROM 1/4 CORNER
FOUND NO EVIDENCE OF M.C.

NO PRIOR SURVEY RECORD KNOWN
TO EXIST OTHER THAN ORIG GOV'T.

TIME SPENT 1 3/4 HR

R/22-23
T 136-227

24
24
0
25

SEPT 29, 1981
D. COULTER
P. BA CON

124

ING

1301

PINE RIVER

NO EVIDENCE OF
M.C. FOUND.
NO VISIBLE LINES
OF OCCUPATION

1003
0110
R-23
T 136-R27

214
24
25

QUARTER COR 24-25/136-27

RAN W. ON MAG FROM APPROX. LOC.
OF M.C. TO EAST. FOUND 5 MON
CORNER IN PLACE. ALL MONUMENTS
ARE 2" IP. OVAL CAPS ON REF. MANS.
ROUND CAP ON 1/4 COR
1/4 COR MON 0.2' BELOW SURFACE
ON SIDE HILL 50' E W. OF TOP OF HILL
REF MANS 0.1 to 0.4 ABOVE SURFACE

NO PRIDE SURVEY RECORD KNOWN TO
EXIST OTHER THAN ORIG GOUT.


TIME SPENT 2 1/2 HRS

R-23
T 136/R27

214
25

SEPT 4, 1981
D. COULTER
P. BACON

126



ALL TREES DOUBLE BLAZED
APPROX. 1' & 5" ABOVE GROUND

125

24
24
25

R/24-25
T 136-R27

MC 24/25-136-27 2.35 CH. W. of SEC CAR
RAN N.W FROM M.C. ON E. LINE of
SEC. TO APPROX. POSITION FOR
THIS M.C. FALLS IN CAMPGROUND
FOUND NO EVIDENCE OF MC

NO PRIOR SURVEY RECORD KNOWN TO
EXIST OTHER THAN ORIG. GOVT.

TIME SPENT 3/4 HR


R/24-25
T 136-R27

24
25

50074, 1981
O. COULTER
P. BALCON

128

NO. S-115



T-21

T136-R27

26-0-25

QUARTER COR 25-26 / 136-27

SEARCHED IN GENERAL AREA
INDICATED BY U.S.G.S QUAD MAP.
FOUND NO EVIDENCE OF CORNER
OTHER THAN OCCUPATION LINES

PRIOR SURVEYS

1902

Whiteley FND INPL

BK W-12, Pg 24

TIME SPENT 1 HR

T-21

T136-R27

26-0-25

SEPT 4, 1981

D. COULTER

P. BACon

NC S-115

WOODED
REMNANTS
OF OLD FENCE
LINES

FOUND NO EVIDENCE
OF MONUMENT

WOODED
FIELD

TREE LINE
TRAIL

GRAVEL
ROAD

WOOD
TRAIL

137
T/U-21
T 136-R27

26-25

MC 25-26/136-27 31.39 CH N. of sec Cor

RAN SOUTH FROM APPROX. POSITION
OF 1/4 COR FOLLOWING TREE &
FENCE LINE. FOUND NO EVIDENCE
OF M.C.

NO PRIOR SURVEY RECORD KNOWN TO EXIST
OTHER THAN ORIG. CONT.

TIME SPENT 3/4 HR

T/U-21
T 136-R27

26-25

Sept 4, 1961
D. COURTES
P. BACON

134

NO. 5-113

