


Crow Wing County Surveyor
No. S-117



11/24/81

INDEX		CONTRACT NO.		PAGE		CORNER DESC.	
SURVEY 40A		S-117				CORNER DESC.	
PAGE	CORNER	DESC.	PAGE	CORNER	DESC.	PAGE	CORNER DESC.
3	C-17	135-28	28	J-13	135-27		
4	G-17	135-28	29	C-21	135-28		
5	P-17	135-28	30	B/C-21	135-28		
6	V/W-17	135-28	31	E-21	135-28		
7	R-16/17	135-28	32	C-25	135-28		
8	Q/R-13	135-28	33	N-24/25	135-28		
9	R-11	135-28	34	N-3	135-27		
10	C-9	135-28	35	P-5	135-27		
11	R-2/13	135-28	36	P-9	135-27		
12	J-2/3	135-28	37	R-9	135-27		
13	P-13	135-29	38	R-9/10	135-27		
14	P/13-13	135-29	39	X-21	135-28		
15	Q/D-1	135-27	40	W/X-21	135-28		
16	E-2/3	135-27	41	V/W-21	135-28		
17	F/G-1	135-27	42	V-2/22	135-28		
18	F/G-1	135-27	43	V-2/24	135-28		
19	J-5	135-27	44	W/X-1	135-27		
20	G-5	135-27	45	V-3	135-27		
21	J/K-5	135-27	46	E-12/13	135-27		
22	L-5	135-27	47	D/E-13	135-27		
23	K/L-5	135-27					
24	N-7	135-27					
25	N-9	135-27					
26	L-9	135-27					
27	J-11	135-27					

③

NOTE:

THIS CONTRACT INCLUDES 12
HOURS SPENT ON CONTRACT
NO. S-III, AFTER S-III WAS COMPLETED
THE INFORMATION FOR
THESE 12 HOURS IS CONTAINED
IN THE FIELD NOTES FOR
CONTRACT NO. S-III.
THE BREAKDOWN FOR THESE
ADDITIONAL 12 HOURS SPENT
ON CONTRACT NO. S-III VS AS
FOLLOWS:

OCT. 8, 1981

ADDITIONAL WORK ON N-21 135-29 2.0 HRS
ADDITIONAL WORK ON P-24 135-29 1.0 HR
ADDITIONAL WORK ON Q/R-21 135-29 1.0 HR

OCT. 19, 1981

ADDITIONAL WORK ON E-3 135-28 2.0 HRS
ADDITIONAL WORK ON K/L-13 135-28 2.0 HRS

OCT. 20, 1981

ADDITIONAL WORK ON V-3/4 135-28 2.0 HRS
ADDITIONAL WORK ON V-5 135-28 2.0 HRS

TOTAL 12.0 HRS

c/p: 17
135
28

3


WE CHAINED NORTH FROM THE
S.W. CORNER OF SEC. 2 - 35-28.
I FOUND A 1/4" PIN @ 660'±
AND A 1" PIPE WITH A BOLT IN
THE TOP @ 1320'±. BOTH ALONG
THE E-W LINE. BUT, SEARCHED
AREA @ 1617' AS PER ORIG. NOTES
DIDNT FIND ANY MONUMENTS OR
ANY EXISTING TRAIL. WE CONTINUED
CHAINING TO THE S.W. SHORE OF PELICAN
LAKE @ 1791'±. I ALSO SEARCHED
ALONG SHORE AREA - NOTHING FOUND
HERE EITHER. THIS AREA IS A
PUBLIC ACCESS WITH CHAIN LINK
FENCE ON BOTH SIDES.

4 HRS.

5, OCTOBER, 1981
+ 50° OVERCAST, LIGHT RAIN
K.P. MCKENZIE
D. MAGNAN

③

PELICAN LAKE



→ S.W. COR. SEC. 2-35-28

135
28

22-23

FOUND IN PLACE GROUNDING CO.
CAST IRON MONUMENT STAMPED
"QUARTER CORNER", APPROX.
0.4' BELOW GRADE AT THE
E. OF CO. RD. 14. I FOUND SEVERAL
TREES THAT APPEARED TO HAVE BEEN
BLAZED BUT NONE TO MATCH
EXIST. RECORDS. SO I TIED OUT
AS SHOWN IN SKETCH.

3 HRS.

9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100

45° P.C.
K.P. MCKENZIE
D. MAGNAN

12" BUR OAK

OAK



V/M-177
1345
25


34 35 36

CHAINED SO. FROM THE S.E.
CORNER OF SEC. 27-135-28
FOUND IN PLACE A 1 1/2" PIPE, UP
0.8' APPROX 605' SO. OF SEC.
COR. SEARCHED AREA 619' S.O.
OF SEC. CORNER, AS PER ORIGINAL
NOTES BUT NO OTHER MONUMENTS.
ALSO FOUND IN PLACE THREE 1"
METAL DISCS, WITH NAILS STAMPED
DNR - R.P. AND I TIED PIPE OUT
TO THESE EXISTING TIES AS SHOWN
IN SKETCH. THE HOME OWNER TO
THE WEST TOLD ME THIS POINT WAS
USED BY THE D.N.R. TO ESTABLISH
A PUBLIC ACCESS TO THE EAST.
AND THAT HE THOUGHT IT WAS THE
M.C.

2 HRS.

6, OCTOBER, 1981
+ 50° P.C.
K.P. MCKENZIE
D. MAGNAN

6



NORTH LONG LAKE

K-1947
135
28


29

CHAINED WEST FROM THE S.E.
CORNER OF SEC. 22-135-28 (A 4" C.I.M.)
APPROX. 904'± WHERE I FOUND A
1/2" PIN FLARED @ THE TOP AND
0.2' BELOW GRADE. THIS POINT FELS
11.5' SO. OF A WIRE FENCE WHICH
RUNS EAST-WEST, ALSO FOUND A 18"
OAK STUMP THAT APPEARS TO BE
THE PT. CALLED AS A 9' OAK
SO. 25-15 E 6895'. BOTH BEARING
AND DIST. FIT VERY WELL. ALSO
LOOKED FOR BUT DIDNT FIND THE
14" NOR. PINE. WE ALSO SEARCHED
THE AREA 948.40' FROM ORIG. NOTES
BUT FOUND NOTHING. WE TIED OUT THIS
POINT AS SHOWN IN SKETCH.

4 hrs.

7 OCTOBER, 1981
+50° CLEAR
K.P. MCKENZIE
D.A. MAGNAN

⑦



Q/R - 13
135
28

21/32

DROVE TO CORNER IN ROAD
FOLLOWED BRUSH LINE IN
THE WOODS. FOUND 1000 SPIKE
NO VISIBLE TIES.

DISTANCE FROM EDGE OF LAKE 136.1

TIED OUT TO FOLLOWING
TREES

POPLAR 4° SOUTH 40° WEST	17.40 FT.
POPLAR 4° NORTH 80° WEST	9.45 FT.
POPLAR 8° SOUTH 85° EAST	22.12 FT.

ALSO CHAINED SOUTH FROM
SECTION CORNER N-13, 135, 28
SOUTH TO NAIL APPROX
4820.00± FEET TO 1000 SPIKE.

4 HRS.

19, OCTOBER, 1981
730° OVERCAST

M. MODEL
B. WESELOH

N-13
135, 28

4820.1

1000 SPIKE

4" POPLAR ABOVE
2.45 N
22.12
8" POPLAR

136.1

MOLLIE LAKE

8


R-11
135
28

21
28
MOLLE
LAKE

CHAINED EAST FROM CORNER S.W.
SECTION 21. FOLLOWED
OLD BARB WIRE FENCE EAST FOR
900 FEET. LEFT FENCE ENTERED
OPEN AREA PLANTED WITH PINE
SAPLINGS. WE WENT 1800 FEET
MORE AND CAME TO EDGE OF
SWAMP OR MARSH, THEN AT 150 FEET
MORE CAME TO FENCE, GOING EAST
AND SOUTH EAST. NOTHING MORE
FOUND

4 HRS.

20, OCTOBER, 1981
+ 47° PARTLY CLOUDY
M.E. HOUEL
B.S. WESELOH



21, OCTOBER, 1981
 +30° OVERCAST, SNOW
 M.E. NOEL
 B.S. WESELOH

(10)

CHAINED NORTH FROM E-9

APPROX 2450 ± FEET ON A

STRAIGHT LINE, ALONG FENCE

BEGINNING AT 1260 ± FEET

AT 2450 ± FEET CAME TO

EDGE OF MARSH & LAKE FILLED

WITH WATER, FOUND NO TIES

ALONG EDGE OF MARSH.

NO CORNER OR EVIDENCE.

3 HRS.



R-12/13

135

28

22

28

27

LOOKED 150[±] FEET NORTH +
SOUTH OF PUBLIC ACCESS
FROM EDGE OF DIAT ROAD
TO EDGE OF LAKE MOLLIE
FOUND NO TIES OR IRONS
TOO WET TO CHAIN FROM
POSSIBLE 4 CORNER TO
WEST. OF MEANDER CORNER
OF MOLLIE LAKE.

2 HRS.


21, OCTOBER, 1981

+30° OVERCAST, SNOW

M.E. HODEL

B.S. WESELOH

(11)




J-213
135
28

CHAINED DOWN FROM ROAD &
TO LAKE, APPROX 300[±] FEET
CAME TO LAKE EDGE. FOUND NOTHING.
SEARCHED WITH METAL LOCATOR.
TALK TO LANDREKER CREW.
THEY WERE TOLD BY AREA RESIDENT
THAT THE SHORE LINE HAS ADVANCED
BY APPROX 20[±] TO 30[±] FEET.
THEY MEASURED DOWN FROM
LOT CORNER FOUND SAME DIST. [±]
AS WE HAD FOUND TO LAKE.
NO CORNER OR EVIDENCE FOUND

2-445

21, OCTOBER, 1981
+30° OVERCAST, SNOW
M.E. MODEL
R.S. WESLOP

(12)



P-13

135-29


21-22

WALKED IN OFF ROAD TO THE WEST
OF 4" PIPE BY NEW FENCE CORNER.
WE WALKED IN APPROX. 250.± FEET
CAME TO OLD WOVEN WIRE FENCE
GOING NORTH & SOUTH. 24.± FEET
TO THE EAST IS AN NEW BARBED
WIRE FENCE GOING NORTH &
EAST. AT THE CORNER OF
NEW FENCE WE FOUND 4" #
IRON PIPE RLS NUMBER 7 SOME-
THING TOO POOR TO READ. ALSO
WE FOUND TWO RED PINES
WITH OLD BLAZES.
ONE 18" RED PINE S79°E 18.80 FEET
ONE 24" RED PINE S78°W 10.61 FEET
WE ALSO PUT A PK IN WEST
SIDE OF FENCE CORNER.
N40°E 1.74 FEET

2 #15

(13)

2, NOV. 1981
+55° CLEAR
M: MOORE
B. WESELOH



NO. 447

W TELEPHONE

P10-13

13529

21-22

CHAINED DUE SOUTH ALONG OLD
WOVEN WIRE FENCE 24' WEST OF
1/4 CORNER FOR SECTION 21+22.
WE WENT APPROX. 1067.00 ± FEET
WE THEN CAME TO TOP OF DUTCHMAN'S
BLUFF AND END OF WOVEN WIRE
FENCE. THERE IS A MOWED YARD
WEST 10' OF FENCE. CHAINED
DOWN HILL APPROX. 140.00 FEET
TO EDGE OF GULL LAKE. HILL IS
FAIRLY STEEP. LOOKED AROUND AT
TOP OF HILL AND AT BOTTOM
FOUND NOTHING. ALSO LOOKED 24'
EAST OF FENCE. FOUND NOTHING.

2-HK


NOV. 2, 1981

M. HOUEL

B. WESELOH

* 55° CLEAR, SUNNY

(14)



C-D-1
T135
R27
MTH

1


6

CHAINED IN DUE SOUTH FROM
P.K. IN CENTER LINE OF
CROW WING COUNTY 118 WENT
APPROX 500 FEET ALONG
DIVISION LINE BETWEEN
TWO PROPERTY OWNERS, CAME TO
EDGE OF WOODS WE WENT APPROX
567 FEET CAME TO NORTH
EDGE OF PERCH LAKE.
WE THEN LOOKED AROUND FOR
BLAZES FOUND NONE. A PROCEEDED
TO USE METAL LOCATOR FOUND
OLD BARB WIRE FENCE ON
THE GROUND, FENCE WAS
GOING NORTH & SOUTH. LOOKED
ALONG FENCE FOUND
NOTHING.

1.5 HRS.

4450 SUNNY
3, NOV. 1981
M. NOBEL
P.K. B. WESELOH

(15)




E-2-3
T135
A-27
5TH

WE DROVE DOWN DRIVEWAY
TO END, TALKED TO LANDOWNER
SHOWED US $1\frac{1}{2}$ " PIPE RLS #3091
ON SECTION LINE 6+7 WEST OF
 $\frac{1}{4}$ CORNER. LOOKED WITH
METAL LOCATOR FOUND NOTHING
BETWEEN PIPE AND LAKE.
LANDOWNER DID NOT KNOW
OF ANY M.C.

1.5 HAS.

+50° SUNNY
3, NOV. 1981
M. NOBEL
B. WESELOH

(16)




F.G. - 1
 7:15
 R. 27
 STH M

TALKED TO LANDOWNER WHO
 SHOWED US THE MC ON THE
 NORTH END OF LAKE EDWARD
 MC. IS IN FIVE GALLON PAIL
 ON CONCRETE AND ROCK RETAINING
 WALL.


TIED OUT TO
 30" RED PINE N. 49° W. 27.57 FEET
 10" RED OAK NORTH BY 56 FEET

SOUTH EAST CORNER HOUSE FOUNDATION
 36.35 FEET



2 HRS.

7:50 SUNNY
 3 NOV. 1981
 M. HOUEL
 G. WESLOH



LAKE EDWARD

F 6-1
T 125
A 25
57N.M.



LOOKED ON SOUTH SHORE OF
PERCH LAKE, ON NORTH LINE
ALONG BARB WIRE FENCE, FROM
M.C. ON NORTH END LAKE EDWARD
T 125-AR 27-57N.M., USED METAL
LOCATOR FOUND 2" IRON PIPE
30" FEET FROM LAKE PERCH
ON BOTTOM OF ICE BANK TIED OUT

TIES ARE P.K.'S IN
6" RED OAK S 20° E 22.22 FEET
6" BARK ASH N 27° W 5.41 FEET
8" TWIN RED OAK S 81° W 21.77 FEET
4" BLACK ASH S 40° E 22.81 FEET

1.5 HRS.

750° SUNNY
3 MAR. 1981
M. MOORE
B. WESELOH

(78)

PERCH LAKE

6" BLACK ASH N 27° W 5.41
540° E
22.81
22.22
520° E

ICE BANK
581° W 21.77
8" TWIN RED OAK

7-5
7:15
8:27
5TH

7 '8
18 | 17

DROVE UP TO TEE IN
ROAD, USED METAL LOCATOR
FOUND 6" X 6" CONC. MONUMENT
MUST BE IRON INSIDE.

TALKED TO MRS. BORDEN
SHE SAID THAT THIS WAS
THE CORNER, ALSO FOUND
BRASS BIT IN A 12" JACK PINE
N 60° W 63.20 FEET.


OTHER TIES ARE
8" RED OAK N 65° E 19.30 FEET
POWER POLE S.W. 50.75 FEET
18" JACK PINE N 15° W 45.14 FEET

8" OAK & 18" JACK PINE HAVE
P.K.'S IN THEM
POWER POLE HAS A NAIL IN IT
OLD TIE?

1.5 HAS.

7:50 SUNNY
3 NOV. 1981
M. HOPEL
B. WESELOM

19



G-5
7:30
APP
5:TH M.

7 8


CLOCKED DOWN WITH SPEED-
OMETER IN TRUCK 1/2 MILE
LOOKED 150* FEET IN EACH
DIRECTION, FOUND NO TIES
OR BLAZES. USED METAL
LOCATOR ON GRAVEL ROAD
FOUND NOTHING. WE THEN
TALKED TO MRS. BARDEN. SHE
SAID THAT THE 1/4 CORNER
WAS NOT IN.

WE CLOCKED DOWN FROM
E-5-735-A-27-5TH

1 HK.

7:55, OVERCAST, FOG
4 NOV. 1981
M. HOUEL
B. WESELOH

(20)



J-K-5
T-136
R-37
5TH M


18. 17

DROVE DOWN GRAVEL ROAD
SOUTH OF J-K-5-T-135-R-37-5TH M
FOR ABOUT 1000[±] FEET CAME
TO A BRANCH IN ROAD, WALKED
DOWN TRAIL FOR ABOUT 250[±] FEET
USING METAL LOCATOR, FOUND
NO TIES OR BLAZES, IT IS
MY OPINION THAT THE MC.
FOR SILVER LAKE IS NOT
NEEDED ANY MORE. THE LAKE
HAS RECEDED 100 TO 200 FEET.
THE SECTION LINE DOES NOT
HIT THE LAKE ANY MORE.

1 PL.

(21)

33, VERNON, MO.
4 NOV 1981
M. MOORE
B. W. ESELOH



L-5
T135
ART
SIN

18 } 17

CLOCKED 1/2 MILE WITH SPEED-
OMETER NORTH, WALKED OFF
ROAD TO WEST LOOKED AROUND
WITH METAL LOCATOR NOTHING
FOUND, LOOKED FOR OLD TIES
FOUND ONE.

FOUND 30" OAK OLD BLAZES
IN IT FACING N.W.
LOOKED ACROSS ROAD FOUND
FIELD & WOOD LINE GOING
EAST & WEST LOOKED AT
PROJECTION OF THIS FIELD
LINE FOUND NOTHING.

130" OAK HAS TWIN BLAZES
AND GRASS B.T. TAG IN BOTTOM.
THIS OAK IS STILL LIVING.
COULD NOT FIND ANY OTHER
TIE TREES OR CORNER.

1 HR.

765° OVERCAST, FOG
4 NOV. 1981
M. MOORE
B. WESELOH

22

SILVER
LAKE

APPROX. LOCATION

WOPS

FIELD

30" BLAZED

OAK LINE

ROAD DEAT

K-L-5
T135
R27
SYNM.

16 } 17

WE LOOKED 400 TO 500 FEET

NORTH OF APPROX. CORNER

L-5-T135-R27-SYNM.

USED METAL LOCATOR FOUND
NOTHING, FOUND NO PLACES.

SILVER LAKE HAS RECORDED

100-200 FEET, IT IS MY

OPINION THAT THE M.C.

IS NOT NEEDED ANY MORE,

AS SECTION LINE WOULD NOT

HIT LAKE.

1 HR.

4 NOV. 1981
A. MOORE
B. WESELOH

(23)

SILVER
LAKE

ROAD
DIRT

APPROX. M.C. LOC.

500 FT

APPROX. 4 LOC.

N-7
T 135
R 27
5TH M.

17
20

CLOCKED EAST FROM N-5-T135-
R27-5TH M. 1/2 MILE.
CAME TO EDGE OF WOODS &
FIELD NORTH & SOUTH OF
CROW WING COUNTY #19.
LOOKED FOR TIES FOUND NONE.
USED METAL LOCATOR 100 ± FEET
EAST & WEST OF DIVISION
LINE LOCATED NOTHING.

1.5 HRS.

455° OVERCAST, FOG
455° OVERCAST, FOG
4. NOV. 1991
M. MODEL
D. WESELOH

24

HEAVILY
WOODED
TOWN HALL
CORN FIELD
CROW WING
COUNTY #19
APPROX. 1/4 CORNER
LOCATION
HEAVILY
WOODED
CORN FIELD

N-9
T135
A127
STHM.


17.16
20 21

CLOCKED EAST FROM N-5
T135-R27. STHM. CLOCKED
1 MILE WITH SPEEDOMETER.
WE THEN CAME TO FORK IN
ROAD ONE GOING NORTH &
ONE GOING SOUTH. USED
METAL LOCATOR ON EXT. OF
CENTER LINE FROM WEST.
I WENT NORTH AND SOUTH
100' FEET AND EAST & WEST
100' FEET NOTHING FOUND.
WE THEN LOOKED FOR TIES
NONE FOUND.

1.5 HRS.

455° SOUTHEAST, FOG.
4, NOV. 1981
M. MODEL
B. WESELOH

25



L-8
T 135
R 22
5TH M.

17.16

CLOCKED NORTH 1/2 MILE FROM
N-9 T135-R22-5TH M.
LOOKED 100± FEET NORTH
SOUTH OF CLOCKED 1/2 MILE
ON ROAD WITH METAL LOCATOR
AND IN WOODS FOR TIES.
WE FOUND NOTHING.
THERE IS A DIVISION
LINE GOING EAST AND WEST
AND FENCES.

1 HR.

+55° OVERCAST
4 NOV. 1981
M. HOUEL
B. WESELOH

(25)

STEEL POST
WOVEN WIRE

CORN
FIELD

TREE LINE

APPROX CORN
LOCATION

WOODS

WOODEN

FENCE

WOODS

TREE LINE

SC. RD. 19
BITUMINOUS

HOUSE

FRONT

YARD

J-11
T135
R27
STNA.

9.
16


CHAINED EAST FROM COUNTY
ROAD TO THE DIST SCALED
OFF QUAD MAP 780 FEET
USED METAL LOCATOR FOUND
NOTHING, WE WENT 200 FEET
EAST AND WEST OF CHAINED
DIST. NO TIES FOUND.
THERE IS A TREE LINE
TO THE SOUTH AT CHAINED
DIST.
TALKED TO LAND OWNER
HE DOES NOT KNOW OF
ANY CORNER HERE.

Z. 5 HRS.

6, NOV. 1981

M. HODEL
B. WESELOH

(27)



J-13

FALL
ART.
STUDY

9

10

16

15

CHAINED IN FROM CENTER

LINE OF CROW WING COUNTY

19 WENT EAST 3,300[±] FEET

FOLLOWED FENCE AND FIELD

LINE CAME TO CORNER IN

FENCE GOING WEST & SOUTH

FOUND NO TIES. USED

COMPASS ON FENCE CORNER,

OLD POWER LINE TO THE

EAST BRUSHED OUT ACROSS RIVER.

TALKED TO LANDOWNER.

HE SAID THERE USED TO

BE A CONCRETE MONUMENT BY

FENCE CORNER BUT IT WAS

MOVED A WHILE AGO.

DID NOT TIE OUT FENCE CORNER.

FENCE IS IN VERY GOOD

CONDITION.

2.5 HRS.

6, NOV. 1981

M. MOORE

B. WESSELOH

(28)

HOUSE

GARAGE

STEEL POST + BARB WIRE

DRIVE WAY

DITCH DRAIN

CORN FIELD

APPROX

CORNER

LOCATION

WOOD FENCE POST

STEEL POST +
BARB WIRE

2


FOUND 2" IRON PIPE, 30' BELOW GROUND,
CORNER FITS AS A P.Z., WITH E. COUNTY
ROAD 118 TO SOUTH AND EAST, ONE OF
DEAN M. ANDERSON TIE TREES FROM
1950 STILL STANDING, IT IS AN 18" WHITE
PINE BEARING NO. 6 S.S. 8 FEET DISTANCE
FITS TO THIS TREE, BOTH BLAZES GROWN
OVER, I DID NOT RE-OPEN BLAZES,
I PUT P.K. NAILS IN SIDE OF
THREE OTHER TIES AS SHOWN
IN SKETCH, DID NOT BLAZE TREES

五

T. 4196-292

Nov. 10, 1981

29




B/C 21

13.5-28

CORNER IS A 2" IRON PIPE .30' ABOVE
GROUND PAINTED RED. THIS CORNER
MEASURES 162.70 FEET NORTH OF
Y4 CORNER (C-21). IT IS 28' FROM
SHORE OF MARKEE LAKE. LAKE APPEARS
TO BE LOWER THAN NORMAL. I DO
NOT FIND ANY VISIBLE TIES FOR
THIS CORNER. I MAKE THREE NEW
TIES AS SHOWN IN SKETCH TIES
ARE P.K. NAILS. IN SIDE OF TREES.
DID NOT BLAZE TREES.

+35°C CLEAR
T. MAGNAN
B. WESELOH
NOV. 10, 1981

(30)



1 HR.

E-21

13.5-28

2

11 12

FOUND 1/2" IRON PIPE WITH CAP #3096

NO VISIBLE TIES FOR THIS

CORNER. COUNTY SURVEYOR RECORDS

RENOTE IRON PIPE IN PLACE IN 1950.

NEIGHBOR TALKED TO US AND

SAID HE THOUGHT THIS IRON

WAS THE SECTION CORNER.

I MADE THREE TIES AS

SHOWN IN SKETCH. TIES ARE

P.K. NAILS IN SIDE OF TREES,

DID NOT BLAZE TREES.

1 HR.

+35° CLEAR

T. MAGNAN

B. WRESELOH

(21)

NOV. 10, 1981

N

GRAVEL ROAD

15" BASSWOOD

19.24
3.0.24

WHITE
HOUSE

580' W.
25.86

20' WILLOW

20.5
22.7

DRIVEWAY

DRIVEWAY

15' APPLE

LAKE EDWARD

135-28

135-27

C-25


135-28

FOUND 1/2" IRON PIPE 10' BELOW GRADE
IN E. CO. RD. 118. FOUND THREE
EXISTING TIES. I TIED CORNER
OUT TO THESE EXISTING TIES
AS SHOWN IN SKETCH.
THE TWO TELEPHONE POLES
HAVE BRASS B.T. TAGS IN THEM.
THE RED OAK HAS A NAIL +
DISC IN SIDE OF TREE, NOT BLAZED.

1 #R.

+ 35° CLEAR
T. MAGNAN
B. WIESELOH
NOV-10-1981

(32)



WIRE FENCE

BROWN
HOUSE

B.T. TAG IN TEL. POLE

WOOD RAIL FENCE

20.81

CO. RD. 118

BITUMINOUS

85.57
570° E

NAIL + DISC IN
SIDE OF 10" RED OAK

B.T. TAG IN TEL. POLE

BLUE
HOUSE

NO. 447

W. T. B. D. N. E.

N-24/25

135-28


13
24

FOLLOWED TRAIL WEST FROM
COORD. #3 AND CO. RD. #19.
FOUND 1/2" PIPE #3091 ALONG TRAIL.
BRUSHLINE GOES WEST TOWARD LAKE
FROM THIS PIPE. AT 300 ± FURTHER
I FIND APPARENT M.C.
BRUSHLINE STOPS AT M.C.
M.C. IS A 1" IRON PIPE UP 1.40 FEET.
IT IS MARKED WITH ALATH AND FLAGGING.
NO VISIBLE TIES NEAR. I MAKE
THREE NEW TIES AS SHOWN IN
SKETCH. TIES ARE TWIN BLADES
FACING CORNER WITH P.K. NAIL
IN BOTTOM BLAZE. TOO WET TO
CHAIN WEST TO ACTUAL WATER
AT SHORE OF LAKE EDWARD.
ESTIMATE SHORE TO BE 250-300 ±
FEET WEST OF M.C.

1 HR.

+3500 CLEAR
T. MAGNAN
B. WESELOH
NOV. 10, 1981

33



N-3

135-27

18

19


I FIND 1" IRON PIPE .10 BELOW GRADE
IN E. COR. #19. I FIND TWO EXISTING
TIES TO THIS CORNER WITH TWIN
BLAZES. BLAZES ARE COMPLETELY
GROWN OVER BUT VERY EVIDENT.
I DID NOT RE-OPEN BLAZES AS
TREES ARE IN LANDOWNER'S FRONT
YARD. THESE BLAZES ARE FACING
THE CORNER. I PUT P.K. NAILS IN
THE SIDE OF THESE TWO
EXISTING TIES AND MAKE
A THIRD TIE AS SHOWN IN
SKETCH IT IS ALSO A P.K.
NAIL IN SIDE OF TREE

1 HA.

T. MAGNAN
B. WESELOH

NOV. 10, 1981

34



P-5
135-22


19 • 20

PROVE TO CORNER LOCATION FROM
ROAD MAP. NO EVIDENCE OF ORIGINAL TIES
OR RESURVEY TIES FOUND. SEARCHED
ENTIRE AREA WITH MAGNETIC LOCATOR,
DID NOT FIND ANY MONUMENT OR
ANY OTHER EVIDENCE OTHER THAN
AS SHOWN ON SKETCH.
FENCE LINE TO SOUTH APPEARS TO
BE QUITE OLD. THIS FENCE LINES
UP WELL WITH BRUSHED OUT TRAIL
TO THE NORTH.

0.5 HAS.

+350 CLEAR
T. MAGNAN
B. WESELOH
NOV. 10, 1981

(35)



P. 9

135-27

284 21

MEASURED NORTH 2640.± FROM
LOCATION OF SOUTHEAST CORNER
SECTION 20. CORNER LOCATION
FALLS IN SWAMPY AREA.
LOOKED FOR ORIGINAL BEARING
TREE. DID NOT FIND IT OR
ANY OTHER EVIDENCE OF
BEARING TREES OR MONUMENTS.
THIS AREA APPEARS TO
BE FLOODED DUE TO
BEAVER DAM.

0.5 HRS.


+35° CLEAR

T. MAGNAN

B. WESELOH

(30)

NOV. 19, 1981



R-9

20 21
29 38

135-27

SEARCHED CORNER LOCATION

FROM QUAD MAP, SEARCHED

ROAD INTERSECTION WITH

MAGNETIC LOCATOR AND

100' ± NORTH AND SOUTH.

I FIND NO MONUMENT AND

NO EVIDENCE OF ORIGINAL

OR RESURVEY BEARING

TREES. CORNER IS EVIDENCED

BY INFORMATION SHOWN

IN SKETCH.

TALKED TO LANDOWNER

THAT OWNS HOUSE; HE HAS

100' ABUTTING SECTION LINE.

HE HAS NEVER SEEN SECTION

CORNER, AND DOESN'T THINK

IT IS IN PLACE.

0.5 HRS.

+35° CLEAR

T. MAGNAN

B. WESELOH

(37)

NOV. 10, 1981

N

10' DIRT ROAD
22' DIRT ROAD
WELL TRAVELED

BRUSHY

POTHOLE
(DEEP CENTER)APPROX.
CORNER
LOCATION

BRUSHY

WOODED

DRIVEWAY


HOUSE

WOODED

MISSISSIPPI RIVER

R-9/10

135-27



SEARCHED AREA ALONG RIVER
ALONG OCCUPATION LINE OF
LANDOWNER. I FIND NO
BEARING TREES AND NO
MONUMENT OR OTHER
EVIDENCE. LANDOWNER THAT
OWNS HOUSE HAS 100' ABUTTING
SECTION LINE. HE HAS NEVER
SEEN M.C. AND DOES NOT
THINK IT IS IN PLACE.
OCCUPATION LINE FITS WELL
WITH EXTENSION OFF
DRIVEWAY AND BEARS EAST-
WEST BY COMPASS CHECK.

0.5 HRS.


+35° CLEAR

T. MAGNAN

B. WESELOH

NOV. 10 1981

58



NO. 447

NATIONAL

X-21
35-28


35-36

I FIND 1" IRON PIPE IN PLACE
UP 0.30' WITH PLASTIC CAP
STAMPEA R.L.S. # 3091. STEEL
FENCE POST NEXT TO CORNER.
STEEL POST FENCE WITH
ELECTRIC WIRE RUNS NORTH
AND EAST FROM CORNER.
I FIND EXISTING TIE TREES
AND TIE TO THESE TREES
AS SHOWN IN SKETCH.
D.N.R. WAS AT THIS CORNER
AND MADE TIES ON FEB. 18, 1901.
I TIE TO THEIR NAIL + DISCS.
TWO OF THESE TIES ALSO
HAVE B.T. TAGS AS INDICATED.


1 HR.

+ 35° CUEAR
T. MAGNAN
B. WESELOH
NOV. 11, 1991

39



ROAD



W/X-21

35 3C

13528

I FIND 1" IRON PIPE IN PLACE
UP 0.20' WITH PLASTIC CAP
STAMPED 'P.L.S. #3091


I FIND EXISTING TIE TREES
AND TIE TO THESE TREES AS
SHOWN IN SKETCH. A.N.R. WAS
AT THIS CORNER AND MADE
TIES ON FEB. 18, 1981.

I TIE TO THEIR NAIL + DISCS.
TWO OF THESE TIES HAVE
B.T. TAGS AS INDICATED.

1 HR.

#350 CLEAR
T. MAGNAN
B. WESELOH
NOV. 11, 1981

40



V/W-21

135-28

35-36

I FIND A 1" IRON PIPE IN PLACE
UP 8.20' WITH A PLASTIC CAP
STAMPED R.L.S. #3091
I FIND EXISTING TIE TREES
AND TIE TO THESE TREES
AS SHOWN IN SKETCH, D.N.R.
WAS AT THIS CORNER AND
MADE TIES ON FEB. 18, 1981.
I USE THEIR NAIL + DISCS.
TWO OF THESE TIES
HAVE B.T. TAGS AS INDICATED


1 HR.

435° CLEAR
T. MAGNAN
B. WESELOH
NOV. 11, 1981

(41)

NO. 445


STATION



135-28


39

1.5 hrs.




V-23/24

13:5-28




I FIND 3" IRON PIPE WITH
ALUMINUM CAP STAMPED M.C.
I FIND TWO EXISTING TIE TREES,
ONE IS AN 9" RED OAK BEARING
S 80° E. THE OTHER IS A 10" JACK
PINE BEARING S 08° W.
BOTH EXISTING TIES HAVE
DOUBLE BLAZES WITH BRASS
B.T. TAGS IN LOWER BLAZES.
I TIE TO THESE TWO EXISTING
TIES AND MAKE A THIRD
TIE CONSISTING OF DOUBLE
BLAZES FACING CORNER
WITH P.K. NAIL IN LOWER BLAZE.
LAKE APPEARS TO BE LOWER
THAN NORMAL, CONSIDERABLE
BEAVER ACTIVITY IN THIS AREA.
ALUMINUM CAP IS MARKED THUS.



1.5 HRS.

1400 CLEAR
T. MAGNAN
B. WESELOH
NOV. 11, 1981

(43)



w/x-1



135-27

48
36
31
7127
7127

I FIND A 1" IRON PIPE IN PLACE
UP 10' WITH PLASTIC CAP
STAMPED P.L.S. # 3091.
I FIND THREE EXISTING
TIE TREES. I TIE M.C.
TO THESE EXISTING TIE
TREES AS SHOWN IN SKETCH.
I MAKE ONE ADDITIONAL
TIE AS ONE EXISTING TIE
IS DEAD. AREA AROUND
CORNER IS COMPLETELY WOODED.

1 HR.

440° CLEAR
T. MAGNAN
B. WESERLOH
NOV. 11, 1981
(44)



CAMPBELL LAKE

V-3

W 135-27

30

31

I FIND 1" IRON PIPE IN PLACE
FLUSH IN OLD HUNTING
ROAD, ROAD BEARS EAST - WEST.



I FIND THREE EXISTING TIE
TREES WITH DOUBLE BLAZES
AND BRASS B.T. TAGS.

I TIE CORNER TO THESE
EXISTING TIE TREES AS
SHOWN IN SKETCH.

1 HR.

140° CLEAR
T. MAGNAN
B. WESELOH
NOV. 11, 1981

(43)



E-12/13
135-27




I GO EAST BY COMPASS BEARING-
FROM EAST END OF TOWNSHIP ROAD.
TOWNSHIP ROAD BEARS EAST-WEST
I FOLLOW FENCE LINE IN PLACE
DOWN TO EDGE OF MISSISSIPPI
RIVER. I FIND NO EVIDENCE OF
ORIGINAL BEARING TREES OR
ANY RESURVEY EVIDENCE.
I FIND NO MONUMENT EITHER.
LANDOWNER NOT HOME TO
QUESTION ABOUT CORNER
LOCATION. USED MAGNETIC
LOCATION 100' E ALONG RIVER
FROM TOP OF BANK TO BOTTOM.
FOUND NOTHING.

2 HRS.

140° CLEAR
T. MARWAN
B. WESLOH
NOV. 12, 1981

(46)



NO. 445

W. 12.50

19

HOUSE

GAR.

TOWN ROAD

CO. RD.

PASTURE

WIRE
FENCE

RIVER

APPROX.
CORNER
LOCATION

